

# PCF85263A

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Rev. 5.2 — 22 September 2021

Product data sheet

## 1 General description

The PCF85263A is a CMOS<sup>1</sup> Real-Time Clock (RTC) and calendar optimized for low power consumption and with automatic switching to battery on main power loss. The RTC can also be configured as a stop-watch (elapsed time counter). Three time log registers triggered from battery switch-over as well as input driven events. Featuring clock output and two independent interrupt signals, two alarms, I<sup>2</sup>C-bus interface and quartz crystal calibration.

For a selection of NXP Real-Time Clocks, see Table 71.

#### 2 Features and benefits

- UL Recognized Component (PCF85263ATL)
- Provides year, month, day, weekday, hours, minutes, seconds and 100th seconds based on a 32.768 kHz quartz crystal
- Stop-watch mode for elapsed time counting. From 100th seconds to 999 999 hours
- Two independent alarms
- · Battery back-up circuit
- · WatchDog timer
- Three timestamp registers
- Two independent interrupt generators plus predefined interrupts at every second, minute, or hour
- · Frequency adjustment via programmable offset register
- Clock operating voltage: 0.9 V to 5.5 V
- Low current; typical 0.28  $\mu$ A at  $V_{DD}$  = 3.0 V and  $T_{amb}$  = 25 °C
- 400 kHz two-line  $I^2$ C-bus interface (at  $V_{DD} = 1.8 \text{ V}$  to 5.5 V)
- Programmable clock output for peripheral devices (32.768 kHz, 16.384 kHz, 8.192 kHz, 4.096 kHz, 2.048 kHz, 1.024 kHz, and 1 Hz)
- Configurable oscillator circuit for a wide variety of quartzes:  $C_L$  = 6 pF,  $C_L$  = 7 pF, and  $C_L$  = 12.5 pF
- Packages offered: SI8, TSSOP8, TSSOP10, HXSON10 and WLCSP12

## 3 Applications

- · Printers and copiers
- Electronic metering
- · Digital cameras
- · White goods
- Elapsed time counter

<sup>1</sup> The definition of the abbreviations and acronyms used in this data sheet can be found in Section 23.



Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

- · Network powered devices
- · Battery backed up systems
- Data loggers
- · Digital voice recorders
- · Mobile equipment
- · Accurate high duration timer

## **Ordering information**

Table 1. Ordering information

Type number	Topside	Package		
	marking	Name	Description	Version
PCF85263AT/A	85263A	SO8	plastic small outline package; 8 leads; body width 3.9 mm	SOT96-1
PCF85263ATL/A	263A	DFN2626-10	plastic thermal enhanced extremely thin small outline package; no leads; 10 terminals; body 2.6 × 2.6 × 0.5 mm	SOT1197-1
PCF85263ATT/A	263A	TSSOP8	plastic thin shrink small outline package; 8 leads; body width 3 mm	SOT505-1
PCF85263ATT1/A	263A	TSSOP10	plastic thin shrink small outline package; 10 leads; body width 3 mm	SOT552-1
PCF85263AUK	F	WLCSP12	wafer level package 12 cu pillars; body 1.19 x 0.94 x 0.22 mm with 0.25 mm pitch	SOT2035-1

## 4.1 Ordering options


Table 2. Ordering options

Type number	Orderable part number	Package	Packing method <sup>[1]</sup>	Minimum order quantity	Temperature
PCF85263AT/A	PCF85263AT/AJ	SO8	Reel 13" Q1 NDP	2500	T <sub>amb</sub> = -40 °C to +85 °C
PCF85263ATL/A	PCF85263ATL/AX	DFN2626-10	Reel 7" Q1 NDP	4000	T <sub>amb</sub> = -40 °C to +85 °C
PCF85263ATT/A	PCF85263ATT/AJ	TSSOP8	Reel 13" Q1 NDP	2500	T <sub>amb</sub> = -40 °C to +85 °C
PCF85263ATT1/A	PCF85263ATT1/AJ <sup>[2]</sup>	TSSOP10	Reel 13" Q1 NDP	2500	$T_{amb}$ = -40 °C to +85 °C
	PCF85263ATT1/AZ	TSSOP10	Reel 13" Q1 NDP SSB <sup>[3]</sup>	2500	$T_{amb}$ = -40 °C to +85 °C
PCF85263AUK	PCF85263AUKZ	WLCSP12	Reel 13" Q1 Dry Pack	20000	$T_{amb}$ = -40 °C to +85 °C

Standard packing quantities and other packaging data are available at www.nxp.com/packages/
Discontinuation Notice 202104010DN; drop in replacement is PCF85263ATT1/AZ. Refer to PCN 202104008A.
This packing method uses a Static Shielding Bag (SSB) solution. Material should be kept in the sealed bag between uses.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus


## 5 Block diagram





Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

## 6 Pinning information


## 6.1 Pinning








Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus





## 6.2 Pin description

Table 3. Pin description

Input or input/output pins must always be at a defined level ( $V_{SS}$  or  $V_{DD}$ ) unless otherwise specified.

Symbol	Pin					Type	Description	
	PCF85263AT (SO8)	PCF85263ATL (DFN2626-10)	PCF85263ATT (TSSOP8)	PCF85263ATT1 (TSSOP10)	PCF85263AUK (WLCSP12)		Primary use	Secondary use
OSCI	1	1	1	1	A2	input	oscillator input	-
osco	2	2	2	2	A3	output	oscillator output	-
VBAT	3	3	3	3	В3	supply	battery backup supply voltage [1]	-
TS (CLK/ĪNTB)	-	4	-	4	C3	input/	can be configured with T	SPM[1:0] <sup>[2]</sup>
						output	timestamp input	INTB and CLK output (push-pull); stop-watch control
VSS	4	5 <sup>[3]</sup>	4	5	D2, D3	supply	ground supply voltage	-
SDA	5	6	5	6	D1	input/ output	serial data line	-
SCL	6	7	6	7	C1	input	serial clock input	-
CLK	-	8	-	8	B2	output	CLK (push-pull)	-
INTA (CLK)	7	9	7	9	B1	output	can be configured with IN	TAPM[1:0] <sup>[4]</sup>
							interrupt output (open-drain)	CLK output (open- drain)
VDD	8	10	8	10	A1, C2	supply	supply voltage	-

PCF85263A

All information provided in this document is subject to legal disclaimers.

© NXP B.V. 2021. All rights reserved.


Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

- [1] Connect to VDD if not used.
- [2] See Table 6 and Table 46.
- The die paddle (exposed pad) is connected to V<sub>SS</sub> through high ohmic (non-conductive) silicon attach and should be electrically isolated. It is good engineering practice to solder the exposed pad to an electrically isolated PCB copper pad as shown in Figure 46 for better heat transfer but it is not required as the RTC doesn't consume much power. In no case should traces be run under the package exposed pad.
- [4] See <u>Table 6</u> and <u>Table 48</u>.

## 7 Functional description


The PCF85263A contains 8-bit registers for time information, for timestamp information and registers for system configuration. Included is an auto-incrementing register address, an on-chip 32.768 kHz oscillator with integrated capacitors, a frequency divider which provides the source clock for the Real-Time Clock (RTC) and calender, and an I<sup>2</sup>C-bus interface with a maximum data rate of 400 kbit/s.

The built-in address register will increment automatically after each read or write of a data byte. After register 2Fh, the auto-incrementing will wrap around to address 00h (see <u>Figure 7</u>).



All registers (see <u>Table 4</u>, <u>Table 5</u>, and <u>Table 6</u>) are designed as addressable 8-bit parallel registers although not all bits are implemented. <u>Figure 8</u> gives an overview of the address map.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus




The 100th seconds, seconds, minutes, hours, days, months, and years as well as the corresponding alarm registers are all coded in Binary Coded Decimal (BCD) format. When one of the RTC registers is read, the contents of all time counters are frozen. Therefore, faulty reading of the clock and calendar during a carry condition is prevented.

#### 7.1 Registers organization overview

#### 7.1.1 Time mode registers

The PCF85263A has two time mode register sets, one for the real-time clock mode and one for the stopwatch clock mode. The access to these registers can be switched by the RTCM bit in the Function control register (28h), see <u>Table 6</u> and <u>Table 53</u>.



Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

## 7.1.1.1 RTC mode time registers overview (RTCM = 0)

Table 4. RTC mode time registers

Bit positions labeled as - are not implemented. After reset, all registers are set according to <u>Table 61</u>.

Address	Register name	Bit								Reference
		7	6	5	4	3	2	1	0	
RTC time a	and date registers									
00h	100th_seconds	100TH_SECO	ONDS (0 to 99)							Section 7.2
01h	Seconds	os	SECONDS (	0 to 59)						
)2h	Minutes	EMON	MINUTES (0	to 59)						
03h	Hours	-	-	AMPM	HOURS (1 to	12) in 12 hour r	node			
				HOURS (0 to	23) in 24 hour m	node				
04h	Days	-	-	DAYS (1 to 3	31)					
05h	Weekdays	-	-	-	-	-	WEEKDAYS	6 (0 to 6)		
06h	Months	-	-	-	MONTHS (1	to 12)				
07h	Years	YEARS (0 to 9	99)		·					
RTC alarm	1	·								
08h	Second_alarm1	-	SEC_ALARM	Л1 (0 to 59)						Section 7.4
09h	Minute_alarm1	-	MIN_ALARM	11 (0 to 59)						
)Ah	Hour_alarm1	-	-	AMPM	HR_ALARM1	(1 to 12) in 12 l	nour mode			
				HR_ALARM	1 (0 to 23) in 24 h	our mode				
0Bh	Day_alarm1	-	-	DAY_ALARN	//1 (1 to 31)					
0Ch	Month_alarm1	-	-	-	MON_ALARM	И1 (1 to 12)				
RTC alarm	2									
0Dh	Minute_alarm2	-	MIN_ALARM	12 (0 to 59)						Section 7.4
)Eh	Hour_alarm2	-	-	AMPM	HR_ALARM2	! (1 to 12) in 12 l	nour mode			
)Fh	Weekday_alarm2	-	-	-	-	-	WDAY_ALA	RM2 (0 to 6)		
RTC alarm	enables									
10h	Alarm_enables	WDAY_A2E	HR_A2E	MIN_A2E	MON_A1E	DAY_A1E	HR_A1E	MIN_A1E	SEC_A1E	Section 7.4
RTC times	tamp1 (TSR1)									
11h	TSR1_seconds	-	TSR1_SECO	ONDS (0 to 59)						Section 7.7
12h	TSR1_minutes	-	TSR1_MINU	TES (0 to 59)					_	
13h	TSR1_hours	-	-	AMPM	TSR1_HOUR	RS (1 to 12) in 12	2 hour mode		_	
				TSR1_HOU	RS (0 to 23) in 24	hour mode				
14h	TSR1_days	-	-	TSR1_DAYS	s (1 to 31)					
15h	TSR1_months	-	-	-	TSR1_MONT	HS (1 to 12)				_
16h	TSR1_years	TSR1_YEARS	6 (0 to 99)							-
RTC times	tamp2 (TSR2)									
17h	TSR2 seconds	-	TSR2 SECO	ONDS (0 to 59)						Section 7.7
18h	TSR2_minutes	-		TES (0 to 59)					_	-
19h	TSR2_hours	-	-	AMPM	TSR2 HOUR	S (1 to 12) in 12	2 hour mode		_	-
	_				RS (0 to 23) in 24	hour mode			_	-
1Ah	TSR2_days	-	_	TSR2 DAYS						_
1Bh	TSR2_months	-	-		TSR2 MONT	THS (1 to 12)				-
1Ch	TSR2_years	TSR2_YEARS	S (0 to 99)		1 - 1 - 1 - 1 - 1 - 1 - 1	- ()				+
	tamp3 (TSR3)		- (3.0.00)							
IDh	TSR3_seconds		TSR3_SECO	ONDS (0 to 59)						Section 7.7
										Occion 7.7
1Eh	TSR3_minutes	-	13K3_IVIIIVU	TES (0 to 59)	TQD2 LIOUE	PS (1 to 12) in 11	) hour mode			-
1Fh	TSR3_hours	-	-	AMPM TSR3_HOURS (1 to 12) in 12 hour mode  TSR3_HOURS (0 to 23) in 24 hour mode				_		
206	TCD2 4					nour mode				-
20h	TSR3_days	-	-	TSR3_DAYS		TIO (4 to 40)				
21h	TSR3_months		- TSR3_MONTHS (1 to 12)							

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

## Table 4. RTC mode time registers...continued

Bit positions labeled as - are not implemented. After reset, all registers are set according to Table 61.

Address	Register name	Bit								Reference
		7	6	5	4	3	2	1	0	
RTC timesta	RTC timestamp mode control									
23h	TSR_mode	TSR3M[1:0]		-	TSR2M[2:0]			TSR1M[1:0]		Section 7.7

## 7.1.1.2 Stop-watch mode time registers (RTCM = 1)

#### Table 5. Stop-watch mode time registers

Bit positions labeled as - are not implemented. After reset, all registers are set according to Table 61.

Address	Register name	Bit								Reference
		7	6	5	4	3	2	1	0	
Stop-watc	h time registers				'			'		
00h	100th_seconds	100TH_SECC	NDS (0 to 99)							Section 7.3
01h	Seconds	os	SECONDS (0	to 59)						
02h	Minutes	EMON	MINUTES (0 t	to 59)						
03h	Hours_xx_xx_00	HR_XX_XX_0	0 (0 to 99)							
04h	Hours_xx_00_xx	HR_XX_00_X	X (0 to 99)							
05h	Hours_00_xx_xx	HR_00_XX_X	X (0 to 99)							
06h	not used	-	-	-	-	-	-	-	-	
07h	not used	-	-	-	-	-	-	-	-	
Stop-watc	h alarm1									
08h	Second_alm1	-	SEC_ALM1 (0	) to 59)						Section 7.4
09h	Minute_alm1	-	MIN_ALM1 (0	to 59)						
0Ah	Hr_xx_xx_00_alm1	HR_XX_XX_0	0_ALM1 (0 to 9	9)					_	
0Bh	Hr_xx_00_xx_alm1	HR_XX_00_X	X_ALM1 (0 to 9	9)					_	
0Ch	Hr_00_xx_xx_alm1	HR_00_XX_X	X_ALM1 (0 to 9	9)						
Stop-watc	h alarm2									
0Dh	Minute_alm2	-	MIN_ALM2 (0	to 59)						Section 7.4
0Eh	Hr_xx_00_alm2	HR_XX_00_A	LM2 (0 to 99)							
0Fh	Hr_00_xx_alm2	HR_00_XX_ALM2 (0 to 99)								
Stop-watc	h alarm enables		_							
10h	Alarm_enables	HR_00_XX_ A2E	HR_XX_00_ A2E	MIN_A2E	HR_00_XX_ XX_A1E	HR_XX_00_ XX_A1E	HR_XX_XX_ 00_A1E	MIN_A1E	SEC_A1E	Section 7.4
Stop-watc	th timestamp1 (TSR1)									
11h	TSR1_seconds	-	TSR1_SECO	NDS (0 to 59)						Section 7.7
12h	TSR1_minutes	-	TSR1_MINUT	ES (0 to 59)						
13h	TSR1_hr_xx_xx_00	TSR1_HR_XX	X_XX_00 (0 to 9	9)						
14h	TSR1_hr_xx_00_xx	TSR1_HR_XX	C_00_XX (0 to 9	9)						
15h	TSR1_hr_00_xx_xx		_XX_XX (0 to 9							
16h	not used	-	-	-	-	-	-	-	-	
Stop-watc	th timestamp2 (TSR2)									
			TODA SECO	NDS (0 to 59)						Section 7.7
17h	TSR2_seconds	-	I SKZ_SECUI							
17h 18h	TSR2_seconds TSR2_minutes	-	TSR2_MINUT							
		- - TSR2_HR_XX	_	ES (0 to 59)						
18h 19h	TSR2_minutes		TSR2_MINUT	ES (0 to 59)						
18h 19h	TSR2_minutes TSR2_hr_xx_xx_00	TSR2_HR_XX	TSR2_MINUT	PS (0 to 59)						
18h 19h 1Ah	TSR2_minutes TSR2_hr_xx_xx_00 TSR2_hr_xx_00_xx	TSR2_HR_XX	TSR2_MINUT C_XX_00 (0 to 99 C_00_XX (0 to 99	PS (0 to 59)	-	-	-	-	-	
18h 19h 1Ah 1Bh	TSR2_minutes TSR2_hr_xx_xx_00 TSR2_hr_xx_00_xx TSR2_hr_00_xx_xx	TSR2_HR_XX	TSR2_MINUT C_XX_00 (0 to 99 C_00_XX (0 to 99	PS (0 to 59)	-	-	-	-	-	
18h 19h 1Ah 1Bh	TSR2_minutes TSR2_hr_xx_xx_00 TSR2_hr_xx_00_xx TSR2_hr_00_xx_xx not used th timestamp3 (TSR3)	TSR2_HR_XX	TSR2_MINUT (_XX_00 (0 to 99) (_00_XX (0 to 99) _XX_XX (0 to 99) -	PES (0 to 59) 9) 9) -	-	-	-	-	-	Section 7.7
18h 19h 1Ah 1Bh 1Ch Stop-watc	TSR2_minutes TSR2_hr_xx_xx_00 TSR2_hr_xx_00_xx TSR2_hr_00_xx_xx not used th timestamp3 (TSR3) TSR3_seconds	TSR2_HR_XX TSR2_HR_00	TSR2_MINUT  (_XX_00 (0 to 9)  (_00_XX (0 to 9)  _XX_XX (0 to 9)  -  TSR3_SECO	99) 99) 99)	-	-	-	-	-	Section 7.7
18h 19h 1Ah 1Bh 1Ch Stop-watc	TSR2_minutes TSR2_hr_xx_xx_00 TSR2_hr_xx_00_xx TSR2_hr_00_xx_xx not used th timestamp3 (TSR3)	TSR2_HR_XX TSR2_HR_00	TSR2_MINUT (_XX_00 (0 to 99) (_00_XX (0 to 99) _XX_XX (0 to 99) -	PES (0 to 59)  9)  9)  10  11  12  13  15  15  15  15  15  15  15  15  15	-	-	-	-	-	Section 7.7

PCF85263A

All information provided in this document is subject to legal disclaimers.

© NXP B.V. 2021. All rights reserved.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 5. Stop-watch mode time registers...continued

Bit positions labeled as - are not implemented. After reset, all registers are set according to Table 61.

Address	Register name	Bit								Reference
		7	6	5	4	3	2	1	0	
21h	TSR3_hr_00_xx_xx	TSR3_HR_00_	SR3_HR_00_XX_XX (0 to 99)							
22h	not used	-	-	-	-	-	-	-	-	
Stop-watch	timestamp mode contro	ol								
23h	TSR_mode	TSR3M[1:0]		-	TSR2M[2:0]			TSR1M[1:0]		Section 7.7

## 7.1.2 Control registers overview

## Table 6. Control and function registers overview

Bit positions labeled as - are not implemented. After reset, all registers are set according to Table 61.

Address	Register name	Bit								Reference
		7	6	5	4	3	2	1	0	
Offset regi	ister									
24h	Offset	OFFSET[7:0]								Section 7.8
Control re	gisters	'								
25h	Oscillator	CLKIV	OFFM	12_24	LOWJ	OSCD[1:0]		CL[1:0]		Section 7.10
26h	Battery_switch	-	-	-	BSOFF	BSRR	BSM[1:0]	'	BSTH	Section 7.11
27h	Pin_IO	CLKPM	TSPULL	TSL	TSIM	TSPM[1:0]	'	INTAPM[1:0	)]	Section 7.12
28h	Function	100TH	PI[1:0]	'	RTCM	STOPM	COF[2:0]	'		Section 7.13
29h	INTA_enable	ILPA	PIEA	OIEA	A1IEA	A2IEA	TSRIEA	BSIEA	WDIEA	Section 7.9
2Ah	INTB_enable	ILPB	PIEB	OIEB	A1IEB	A2IEB	TSRIEB	BSIEB	WDIEB	Section 7.9
2Bh	Flags	PIF	A2F	A1F	WDF	BSF	TSR3F	TSR2F	TSR1F	Section 7.14
RAM byte		'		'				'	'	
2Ch	RAM_byte	B[7:0]								Section 7.6
WatchDog	registers	'								
2Dh	WatchDog	WDM	WDR[4:0]					WDS[1:0]		Section 7.5
Stop		'	'					'		'
2Eh	Stop_enable	-	-	-	-	-	-	-	STOP	Section 7.16
Reset	-									
2Fh	Resets	CPR	0	1	0	SR	1	0	CTS	Section 7.15

## 7.2 RTC mode time and date registers

RTC mode is enabled by setting RTCM = 0. These registers are coded in the BCD format to simplify application use.

Default state is:

Time: 00:00:00.00

Date: 2000 01 01

Weekday: Saturday

**Monitor bits**: OS = 1, EMON = 0

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 7. Time and date registers in RTC mode (RTCM = 0)

Bit positions labeled as - are not implemented and return 0 when read.

Address	Register name	Upper-	digit (ter	ı's place	·)	Digit (u	nit place	e)	
		Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
00h	100th_seconds	0 to 9				0 to 9			
01h	Seconds	os	0 to 5			0 to 9			
02h	Minutes	EMON	0 to 5			0 to 9			
03h	Hours [2]	-	-	AMPM	0 to 1	0 to 9			
				0 to 2	'	0 to 9			
04h	Days <sup>[3]</sup>	-	-	0 to 3		0 to 9			
05h	Weekdays	-	-	-	-	-	0 to 6		
06h	Months	-	-	-	0 to 1	0 to 9	'		
07h	Years	0 to 9			,	0 to 9			

<sup>[1]</sup> The 100th\_seconds register is only available when the 100TH mode is enabled, see Section 7.13.1. When the 100TH mode is disabled, this register always returns 0.

#### 7.2.1 Definition of BCD

The Binary-Coded Decimal (BCD) is an encoding of numbers where each digit is represented by a separate bit field. Each bit field may only contain the values 0 to 9. In this way, decimal numbers and counting is implemented.

Example: 59 encoded as an entire number is represented by 3Bh or 11 1011. In BCD the 5 is represented as 5h or 0101 and the 9 as 9h or 1001 which combines to 59h.

Table 8. BCD coding

Value in	Upper-o	ligit (ten's	place)		Digit (u	ınit place)		
decimal	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
00	0	0	0	0	0	0	0	0
01	0	0	0	1	0	0	0	1
02	0	0	1	0	0	0	1	0
:	:	:	:	:	:	:	:	:
09	1	0	0	1	1	0	0	1
10	0	0	0	0	0	0	0	0
:	:	:	:	:	:	:	:	:
98	1	0	0	1	1	0	0	0
99	1	0	0	1	1	0	0	1

#### 7.2.2 OS: Oscillator stop

When the oscillator of the PCF85263A is stopped, the OS status bit is set. The oscillator can be stopped, for example, by connecting one of the oscillator pins OSCI or OSCO to


<sup>[2]</sup> Hour mode is set by the 12\_24 bit in the Oscillator register, see Section 7.10.

<sup>[3]</sup> If the year counter contains a value, which is exactly divisible by 4, the PCF85263A compensates for leap years by adding a 29th day to February.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

ground. The oscillator is considered to be stopped during the time between power-on and stable crystal resonance. This time can be in the range of 200 ms to 2 s depending on crystal type, temperature, and supply voltage.

The status bit remains set until cleared by command (see <u>Figure 10</u>). If the bit cannot be cleared, then the oscillator is not running. This method can be used to monitor the oscillator and to determine if the supply voltage has reduced to the point where oscillation fails.



#### 7.2.3 EMON: event monitor

The EMON can be used to monitor the status of all the flags in the Flags register, see Section 7.14. When one or more of the flags is set, then the EMON bit returns a logic 1. The EMON bit cannot be cleared. EMON returns a logic 0 when all flags are cleared.

See Figure 23 for a pictorial representation.

## 7.2.4 Definition of weekdays

Definition may be reassigned by the user.

Table 9. Weekday assignments

Day	Bit		
	2	1	0
Sunday	0	0	0
Monday	0	0	1
Tuesday	0	1	0
Wednesday	0	1	1
Thursday	1	0	0
Friday	1	0	1
Saturday	1	1	0

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus


#### 7.2.5 Definition of months

Table 10. Month assignments in BCD format

Month	Upper-digit (ten's place)	Digit (unit place	ce)		
	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
January	0	0	0	0	1
February	0	0	0	1	0
March	0	0	0	1	1
April	0	0	1	0	0
May	0	0	1	0	1
June	0	0	1	1	0
July	0	0	1	1	1
August	0	1	0	0	0
September	0	1	0	0	1
October	1	0	0	0	0
November	1	0	0	0	1
December	1	0	0	1	0

## 7.2.6 Setting and reading the time in RTC mode

Figure 11 shows the data flow and data dependencies starting from the 100 Hz clock tick.



Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

During read operations, the time counting circuits (memory locations 00h through 07h) are copied into an output register. The RTC continues counting in the background.

When reading or writing the time it is very important to make a read or write access in one go, that is, setting or reading 100th seconds through to years should be made in one single access. Failing to comply with this method could result in the time becoming corrupted.

As an example, if the time (seconds through to hours) is set in one access and then in a second access the date is set, it is possible that the time increments between the two accesses. A similar problem exists when reading. A roll-over may occur between reads thus giving the minutes from one moment and the hours from the next.

Before setting the time, the STOP bit should be set and the prescalers should be cleared (see Section 7.16).

An example of setting the time: 14 hours, 23 minutes and 19 seconds.

- I<sup>2</sup>C START condition
- I<sup>2</sup>C target address + write (A2h)
- · register address (2Eh)
- write data (set STOP, 01h)
- · write data (clear prescaler, A4h)
- write data (100th seconds, 00h)
- write data (Hours, 14h)
- write data (Minutes, 23h)
- write data (Seconds, 19h)
- I<sup>2</sup>C START condition
- I<sup>2</sup>C target address + write (A2h)
- register address (2Eh)
- write data (clear STOP, 00h). Time starts counting from this point
- I<sup>2</sup>C STOP condition

#### 7.3 Stop-watch mode time registers

These registers are coded in the BCD format to simplify application use.

Stop-watch mode is enabled by setting RTCM = 1. In stop-watch mode, the PCF85263A counts from 100th seconds to 99 9 999 hours. There are no days, weekdays, months or year registers.

Default state is:

#### Time

00.000:00:00.00

#### **Monitor bits**

OS = 1, EMON = 0 (see Section 7.2.2 and Section 7.2.3)

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 11. Time registers in stop-watch mode (RTCM = 1)

Bit positions labeled as - are not implemented and return 0 when read.

Address	Register name	Upper-c	Upper-digit (ten's place)			Digit (unit place)			
		Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
00h	100th_seconds [1]	0 to 9	0 to 9			0 to 9			
01h	Seconds	os	OS 0 to 5			0 to 9			
02h	Minutes	EMON	EMON 0 to 5			0 to 9			
03h	Hours_xx_xx_00	0 to 9				0 to 9			
04h	Hours_xx_00_xx	0 to 9				0 to 9			
05h	Hours_00_xx_xx	0 to 9				0 to 9			
06h	not used	-	-	-	-	-	-	-	-
07h	not used	-	-	-	-	-	-	-	-

<sup>[1]</sup> The 100th\_seconds register is only available when the 100TH mode is enabled, see Section 7.13.1. When the 100TH mode is disabled, this register always returns 0.

#### 7.3.1 Setting and reading the time in stop-watch mode


Figure 12 shows the data flow and data dependencies starting from the 100 Hz clock tick.

During read operations, the time counting circuits (memory locations 00h through 07h) are copied into an output register. The RTC continues counting in the background.

When reading or writing the time it is very important to make a read or write access in one go, that is, setting or reading 100th\_seconds through to HR\_00\_xx\_xx should be made in one single access. Failing to comply with this method could result in the time becoming corrupted.

As an example, if the seconds value is set in one access and then in a following access the minutes value is set, it is possible that the time increments between the two accesses. A similar problem exists when reading. A roll-over may occur between reads thus giving the seconds from one moment and the minutes from the next.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus



#### 7.4 Alarms

There are two independent alarms. Each is separately configured and may be used to generate an interrupt. In RTC mode, an alarm is configured for time and date. In stop-watch mode when the RTC is functioning as an elapsed time counter, an alarm is configured for time only.

#### 7.4.1 Alarms in RTC mode

In RTC mode, Alarm 1 can be configured from seconds to months. Alarm 2 operates on minutes, hours and weekday. Each segment of the time is independently enabled. Alarms can be output on the  $\overline{\text{INTA}}$  and  $\overline{\text{INTB}}$  pins.

#### 7.4.1.1 Alarm1 and alarm2 registers in RTC mode

Setting the time for alarm1: Only the information which is relevant for the alarm condition must to be programmed. The unused parts are ignored.

Table 12. Alarm1 and alarm2 registers in RTC mode coded in BCD (RTCM = 0) Bit positions labeled as - are not implemented.

Address	Register name	Upper-o	Upper-digit (ten's place)			Digit (unit place)			
		Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
RTC alarn	RTC alarm1 registers							,	
08h	Second_alarm1	-	0 to 5			0 to 9			
09h	Minute_alarm1	_	0 to 5			0 to 9			
0Ah	Hour_alarm1	-	-	AMPM	0 to 1	0 to 9			
				0 to 2		0 to 9			

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 12. Alarm1 and alarm2 registers in RTC mode coded in BCD (RTCM = 0)...continued Bit positions labeled as - are not implemented.

Address	Register name	Upper-digit (ten's place)				Digit (unit place)			
		Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
0Bh	Day_alarm1	-	-	0 to 3		0 to 9			
0Ch	Month_alarm1	-	-	-	0 to 1	0 to 9			
RTC alarn	n2 registers								
0Dh	Minute_alarm2	-	0 to 5	_		0 to 9			
0Eh	Hour_alarm2	-	-	AMPM	0 to 1	0 to 9			
				0 to 2		0 to 9			-
0Fh	Weekday_alarm2	-	_	-	_	_	0 to 6		

#### 7.4.1.2 Alarm1 and alarm2 control in RTC mode

Table 13. Alarm\_enables- alarm enable control register (address 10h) bit description

Bit	Symbol	Value	Description	
RTC	alarm2			
7	WDAY_A2E		weekday alarm2 enable	
		0 <sup>[1]</sup>	disabled	
		1	enabled	
6	HR_A2E		hour alarm2 enable	
		0 [1]	disabled	
		1	enabled	
5	MIN_A2E		minute alarm2 enable	
		0 [1]	disabled	
		1	enabled	
RTC	alarm1			
4	MON_A1E		month alarm1 enable	
		0 [1]	disabled	
		1	enabled	
3	DAY_A1E		day alarm1 enable	
		0 <sup>[1]</sup>	disabled	
		1	enabled	
2	HR_A1E		hour alarm1 enable	
		0 [1]	disabled	
		1	enabled	
1	MIN_A1E		minute alarm1 enable	
		0 [1]	disabled	
		1	enabled	

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 13. Alarm\_enables- alarm enable control register (address 10h) bit description...continued

Bit	Symbol	Value	Description
0	SEC_A1E		second alarm1 enable
		0 [1]	disabled
		1	enabled

<sup>[1]</sup> Default value.

#### 7.4.1.3 Alarm1 and alarm2 function in RTC mode

The registers at addresses 08h through 0Ch contain alarm1 information. When one or more of these registers is loaded with second, minute, hour, day, or month, and its corresponding alarm enable bit (SEC\_A1E to MON\_A1E) is set logic 1, then that information is compared with the current second, minute, hour, day, and month.


The registers at addresses 0Dh through 0Fh contain alarm2 information. When one or more of these registers is loaded with minute, hour or weekday, and its corresponding alarm enable bit (MIN\_A2E to WDAY\_A2E) is set logic 1, then that information is compared with the current minute, hour and weekday.

Alarm registers which have their alarm enable bit at logic 0 are ignored.

When the time increments to match the enabled alarms, the alarm flag in the Flags register (Section 7.14) is set. A1F for alarm1 and A2F for alarm2. The alarm flag is cleared by command.

When the time increments to match the enabled alarms, an interrupt can be generated. See Section 7.4.3.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus



#### 7.4.2 Alarms in stop-watch mode

In stop-watch mode, Alarm 1 can be configured from seconds to 999 999 hours. Alarm 2 operates on minutes up to 9 999 hours.

#### 7.4.2.1 Alarm1 and alarm2 registers in stop-watch mode

Setting the time for alarm1 and alarm2: Only the information which is relevant for the alarm condition must to be programmed. The unused parts are ignored.

PCF85263A

All information provided in this document is subject to legal disclaimers.

© NXP B.V. 2021. All rights reserved.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 14. Alarm1 and alarm2 registers in stop-watch mode coded in BCD (RTCM = 1)

Bit positions labeled as - are not implemented.

Address	Register name	Upper-digit (ten's place)				Digit (unit place)			
		Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
Stop-wate	Stop-watch alarm1 registers								
08h	Second_alm1	-	0 to 5	_		0 to 9			
09h	Minute_alm1	-	0 to 5			0 to 9			
09h	Hr_xx_xx_00_alm1	0 to 9				0 to 9			
0Bh	Hr_xx_00_xx_alm1	0 to 9				0 to 9			
0Ch	Hr_00_xx_xx_alm1	0 to 9				0 to 9			
Stop-wate	ch alarm2 registers					·			
0Dh	Minute_alm2	-	0 to 5			0 to 9			
0Eh	Hr_xx_00_alm2	0 to 9				0 to 9			
0Fh	Hr_00_xx_alm2	0 to 9				0 to 9			

#### 7.4.2.2 Alarm1 and alarm2 control in stop-watch mode

Table 15. Alarm\_enables- alarm enable control register (address 10h) bit description

Bit	Symbol	Value	Description
Stop-v	vatch alarm2		
7	HR_00_XX_A2E		thousands of hours alarm2 enable
		0 [1]	disabled
		1	enabled
6	HR_XX_00_A2E		tens of hours alarm2 enable
		0 [1]	disabled
		1	enabled
5	MIN_A2E		minute alarm2 enable
		0 [1]	disabled
		1	enabled
Stop-v	vatch alarm1		
4	HR_00_XX_XX_A1E		100 thousands of hours alarm1 enable
		0 [1]	disabled
		1	enabled
3	HR_XX_00_XX_A1E		thousands of hours alarm1 enable
		0 [1]	disabled
		1	enabled

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 15. Alarm\_enables- alarm enable control register (address 10h) bit description...continued

Bit	Symbol	Value	Description
2	HR_XX_XX_00_A1E		tens of hour alarm1 enable
		0 [1]	disabled
		1	enabled
1	MIN_A1E		minute alarm1 enable
		0 [1]	disabled
		1	enabled
0	SEC_A1E		second alarm1 enable
		0 [1]	disabled
		1	enabled

<sup>[1]</sup> Default value.

#### 7.4.2.3 Alarm1 and alarm2 function in stop-watch mode

The registers at addresses 08h through 0Ch contain alarm1 information. When one or more of these registers is loaded with second, minute, and hours, and its corresponding alarm enable bit (SEC\_A1E to HR\_00\_XX\_XX\_A1E) is set logic 1, then that information is compared with the current second, minute, and hours.


The registers at addresses 0Dh through 0Fh contain alarm2 information. When one or more of these registers is loaded with minute and hours, and its corresponding alarm enable bit (MIN\_A2E to HR\_00\_XX\_A2E) is set logic 1, then that information is compared with the current minute and hours.

Alarm registers which have their alarm enable bit at logic 0 are ignored.

When the time increments to match the enabled alarms, the alarm flag in the Flags register (Section 7.14) is set. A1F for alarm1 and A2F for alarm2. The alarm flag is cleared by command.

When the time increments to match the enabled alarms, an interrupt can be generated. See Section 7.4.3.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus



#### 7.4.3 Alarm interrupts

The generation of interrupts from the alarm functions is controlled via the alarm interrupt enable bits; A1IEA, A1IEB, A2IEA, A2IEB. These bits are in registers INTA\_enable (address 29h) and INTB\_enable (address 2Ah).

The assertion of flags A1F or A2F can be used to generate an interrupt at the pins  $\overline{\text{INTA}}$  and  $\overline{\text{INTB}}$ . The interrupt may be generated as a pulse signal every time the time

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

increments to match the alarm setting or as a permanently active signal which follows the condition of bit A1F and/or A2F. See <u>Section 7.9</u> for interrupt control.

A1F and A2F remain set until cleared by command. Once an alarm flag has been cleared, it will only be set again when the time increments to match the alarm condition once more.

When an interrupt pin is configured to pulse mode and if an alarm flag is not cleared and the time increments to match the alarm condition again, then a repeated interrupt pulse will be generated.

## 7.5 WatchDog

Table 16. WatchDog - WatchDog control and register (address 2Dh) bit description

Bit	Symbol	Value	Description
7	WDM		WatchDog mode
		0 [1]	single shot
		1	repeat mode
6 to 2	WDR[4:0]		WatchDog register bits
		0h <sup>[1]</sup> to 1Fh	Write: WatchDog counter load value
		0h to 1Fh	Read: current counter value
1 to 0	WDS[1:0]		WatchDog step size (source clock)
		00 [1]	4 seconds (0.25 Hz)
		01	1 second (1 Hz)
		10	1/ <sub>4</sub> second (4 Hz)
		11	<sup>1</sup> / <sub>16</sub> second (16 Hz)

<sup>[1]</sup> Default value.

#### 7.5.1 WatchDog functions

The WatchDog has four selectable step sizes allowing for periods in the range from 62.5 ms to 124 seconds. For periods greater than 2 minutes, the alarm function can be used.

$$WatchDog-duration = WDR \times stepsize$$
 (1)

Table 17. WatchDog durations

WDS[1:0]	WatchDog step size [1]	Delay					
size · ·		Minimum WatchDog duration WDR = 1	Maximum WatchDog duration WDR = 31				
00	4 s	4 s	124 s				
01	1 s	1 s	31 s				
10	1/ <sub>4</sub> s	0.25 s	7.75 s				
11	<sup>1</sup> / <sub>16</sub> s	0.0625 s	1.9375 s				

<sup>[1]</sup> Time periods can be affected by correction pulses.

PCF85263A


All information provided in this document is subject to legal disclaimers.

© NXP B.V. 2021. All rights reserved

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

**Remark:** Note that all timings are generated from the 32.768 kHz oscillator and are based on the assumption that there is 0 ppm deviation. Deviation in oscillator frequency results in deviation in timings. This is not applicable to interface timing.

The WatchDog counts down from a software-loaded 5-bit binary value, WDR[4:0], in register WatchDog. Loading the counter with 0 stops the WatchDog. Loading the counter with a non-0 value starts the counter. Values from 1 to 31 are allowed.



If a new value of WDR[4:0] is written before the end of the current WatchDog period, then this value takes immediate effect.

When starting the timer for the first time or when reloading WDR[4:0] before the end of the current period, the first period has an uncertainty of maximum one count. The uncertainty is a result of loading the WDR[4:0] from the interface clock which is asynchronous from the WatchDog source clock. Subsequent WatchDog periods do not have such variation.

Reading the WatchDog register returns the current value of the WatchDog counter (see <u>Figure 15</u>) and **not** the initial value WDR[4:0]. Since it is not possible to freeze the WatchDog counter during read back, it is recommended to read the register twice and check for consistent results.


#### 7.5.1.1 WatchDog repeat mode

In repeat mode, at the end of every WatchDog period, the WatchDog flag (bit WDF in the Flags register, Section 7.14) is set and the counter automatically reloads and starts the next WatchDog period. An example is given in Figure 15. The asserted bit WDF can be used to generate an interrupt. Bit WDF can only be cleared by command.

#### 7.5.1.2 WatchDog single shot mode

In single shot mode, at the end of the countdown period, the WatchDog flag (bit WDF in the Flags register, <u>Section 7.14</u>) is set and the counter stops with the value 0. The WatchDog register must be reloaded to start another WatchDog period.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus



#### 7.5.1.3 WatchDog interrupts

The generation of interrupts from the WatchDog functions is controlled via the WatchDog interrupt enable bits; WDIEA and WDIEB. These bits are in registers INTA\_enable (address 29h) and INTB\_enable (address 2Ah).

The assertion of the flag WDF can be used to generate an interrupt at pins  $\overline{\text{INTA}}$  and  $\overline{\text{INTB}}$ . The interrupt may be generated as a pulsed signal every time the WatchDog counter reaches the end of the countdown period. Alternatively as a permanently active signal which follows the condition of bit WDF. WDF remains set until cleared by command.

When enabled, interrupts are triggered every time the WatchDog counter reaches the end of the countdown period and even if the WDF is not cleared, an interrupt pulse can be generated.

See <u>Section 7.9</u> for interrupt control.

#### 7.6 RAM byte

Table 18. RAM byte - 8-bit RAM register (address 2Ch) bit description

Bit	Symbol	Value	Description
7 to 0	B[7:0]	0000 0000 <sup>[1]</sup> to 1111 1111	RAM content

[1] Default value.

The PCF85263A provides a free RAM byte, which can be used for any purpose, for example, status bits of the system.

#### 7.7 Timestamps

There are three timestamp registers which can be independently configured to record the time for battery switch-over events and/or transitions on the TS pin.


Each timestamp register has an associated flag. It is also possible to generate an interrupt signal for every timestamp register update.

PCF85263A

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Timestamps work in both RTC and stop-watch mode. During battery operation, the mechanical switch detector may also be used to trigger the timestamp.

The timestamp registers are read only and cannot be written. It is possible to set all three registers to 0 with the CTS instruction in the Resets register (Section 7.15).



The mode for each register is controlled by the TSR\_mode register.

Table 19. TSR\_mode - timestamp mode control register (address 23h) bit description

Bit	Symbol	Value	Description					
Timesta	Timestamp3 (TSR3)							
7 to 6	7 to 6 TSR3M[1:0]		timestamp register 3 mode					
		00 [1]	no timestamp					
		01	FB, record <b>F</b> irst time switch to <b>B</b> attery event					
		10	LB, record Last time switch to Battery event					
		11	LV, record <b>L</b> ast time switch to $\mathbf{V}_{DD}$ event					
5	-	0	not used					

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 19. TSR\_mode - timestamp mode control register (address 23h) bit description...continued

Bit	Symbol	Value	Description
Timesta	amp2 (TSR2)		
4 to 2	TSR2M[2:0]		timestamp register 2 mode
		000 [1]	no timestamp
		001	FB, record <b>F</b> irst time switch to <b>B</b> attery event
		010	LB, record <b>L</b> ast time switch to <b>B</b> attery event
		011	LV, record Last time switch to $\mathbf{V}_{DD}$ event
		100	FE, record First TS pin Event
		101	LE, record Last TS pin Event
		110 to 111	no timestamp
Timesta	amp1 (TSR1)		
1 to 0	TSR1M[1:0]		timestamp register 1 mode
		00 [1]	no timestamp
		01	FE, record First TS pin Event
		10	LE, record Last TS pin Event
		11	no timestamp


<sup>[1]</sup> Default value.


**First event** means that the time is only stored on the first event and not recorded for subsequent events. When the first event occurs, the associated timestamp flag is set. When the flag is cleared, then a new 'first' event is recorded. See <u>Figure 18</u> and <u>Figure 19</u>.

**Last event** means that the time is stored on every event. When an event occurs, the associated timestamp flag is set. It is not necessary to clear the flag before a new event is recorded.

Interrupts can be generated in  $\overline{\text{INTA}}$  pin and/or  $\overline{\text{INTB}}$  pin. Interrupts are generated every time a timestamp register is updated. Interrupt generation is not conditional on the state of the timestamp flags. See Section 7.7.1.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus





The recorded time is stored in the associated timestamp register. The time format depends on the RTC mode. The timestamp registers follows the time format of the time registers.

Table 20. Timestamp registers in RTC mode (RTCM = 0)

Bit positions labeled as - are not implemented and return 0 when read.

Address	Register name	Upper-digit (ten's place)			Digit (unit place)					
		Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	
RTC times	RTC timestamp1 (TSR1)									
11h	TSR1_seconds	-	0 to 5		-	0 to 9				
12h	TSR1_minutes	-	0 to 5			0 to 9				

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 20. Timestamp registers in RTC mode (RTCM = 0)...continued Bit positions labeled as - are not implemented and return 0 when read.

Address	Register name	Upper-	digit (ter	ı's place	)	Digit (unit place)			
		Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
13h	TSR1_hours	SR1_hours		AMPM	0 to 1	0 to 9		-	_
				0 to 2		0 to 9			
14h	TSR1_days	-	-	0 to 3		0 to 9			
15h	TSR1_months	-	-	-	0 to 1	0 to 9			
16h	TSR1_years	0 to 9				0 to 9			
RTC times	stamp2 (TSR2)								
17h	TSR2_seconds	-	0 to 5			0 to 9			
18h	TSR2_minutes	-	0 to 5	o 5		0 to 9			
19h	19h TSR2_hours	-	-	AMPM	0 to 1	0 to 9			
			0 to 2			0 to 9			
1Ah	TSR2_days	-	-	0 to 3		0 to 9			
1Bh	TSR2_months	-	-	-	0 to 1	0 to 9			
1Ch	TSR2_years	0 to 9			,	0 to 9			
RTC times	stamp3 (TSR3)								
1Dh	TSR3_seconds	-	0 to 5	_		0 to 9			
1Eh	TSR3_minutes	-	0 to 5			0 to 9			
1Fh	TSR3_hours	-	-	AMPM	0 to 1	0 to 9			
				0 to 2		0 to 9			
20h	TSR3_days	-	-	0 to 3		0 to 9			
21h	TSR3_months	-	-	-	0 to 1	0 to 9			
22h	TSR3_years	0 to 9				0 to 9			

Table 21. Timestamp registers in stop-watch mode (RTCM = 1)

Bit positions labeled as - are not implemented and return 0 when read.

Address	Register name	Upper-digit (ten's plac			e)	Digit (unit place)						
		Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0			
Stop-wat	Stop-watch timestamp1 (TSR1)											
11h	TSR1_seconds	-	0 to 5			0 to 9						
12h	TSR1_minutes	-	0 to 5			0 to 9						
13h	TSR1_hr_xx_xx_00	0 to 9				0 to 9						
14h	TSR1_hr_xx_00_xx	0 to 9				0 to 9						
15h	TSR1_hr_00_xx_xx	0 to 9	9		0 to 9							
16h	not used	-	-	-	-	-	-	-	-			

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 21. Timestamp registers in stop-watch mode (RTCM = 1)...continued Bit positions labeled as - are not implemented and return 0 when read.

Address	Register name	Upper-	digit (te	n's plac	:e)	Digit (unit place)			
		Bit 7	Bit 7 Bit 6 Bit 5 Bit 4		Bit 3	Bit 2	Bit 1	Bit 0	
Stop-wate	ch timestamp2 (TSR2	2)	,						
17h	TSR2_seconds	-	0 to 5			0 to 9			
18h	TSR2_minutes	-	0 to 5			0 to 9			
19h	TSR2_hr_xx_xx_00	0 to 9				0 to 9			
1Ah	TSR2_hr_xx_00_xx	0 to 9				0 to 9			
1Bh	TSR2_hr_00_xx_xx	0 to 9				0 to 9			
1Ch	not used	-	-	-	-	-	-	-	-
Stop-wate	ch timestamp3 (TSR3	3)							
1Dh	TSR3_seconds	-	0 to 5	_		0 to 9	_		
1Eh	TSR3_minutes	-	0 to 5			0 to 9			
1Fh	TSR3_hr_xx_xx_00	0 to 9				0 to 9			
20h	TSR3_hr_xx_00_xx	0 to 9		0 to 9					
21h	TSR3_hr_00_xx_xx	0 to 9	0 to 9		0 to 9				
22h	not used	-	-	-	-	-	-	-	-

## 7.7.1 Timestamps interrupts

The generation of interrupts from the timestamp functions is controlled via the timestamp interrupt enable bits; TSRIEA and TSRIEB. These bits are in registers INTA\_enable (address 29h) and INTB\_enable (address 2Ah).

The loading of new information into one of the timestamp registers can be used to generate an interrupt at pins  $\overline{\text{INTA}}$  and  $\overline{\text{INTB}}$ . The interrupt may be generated as a pulsed signal every time a timestamp register updates or as a permanently active signal which follows the condition of timestamp flags, TSR1F to TSR3F. The timestamp flags remain set until cleared by command.

When enabled, interrupts are triggered every time a timestamp register updates and even if the associated flag is not cleared, an interrupt pulse can be generated.

See Section 7.9 for interrupt control.

#### 7.8 Offset register

The PCF85263A incorporates an offset register (address 24h) which can be used to implement several functions, such as:

- · Accuracy tuning
- · Aging adjustment
- · Temperature compensation

Table 22. Offset - offset register (address 24h) bit description

Bit	Symbol	Value	Description
7 to 0	OFFSET[7:0]	see <u>Table 24</u>	offset value

PCF85263A

All information provided in this document is subject to legal disclaimers.

© NXP B.V. 2021. All rights reserved

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

There are two modes which define the correction period, normal mode and fast mode. The **normal mode** is suitable for offset trimming. The **fast mode** is suitable for dynamic offset correction e.g. implementing a temperature correction. The fast mode consumes more current. Offset mode is defined by bit OFFM in the Oscillator register (Section 7.10).

Table 23. OFFM bit - oscillator control register (address 25h) See Section 7.10

Bit	Symbol	Value	Description
6	OFFM		offset mode bit
		0 [1]	normal mode: correction is made every 4 hours; 2.170 ppm/step
		1	fast mode: correction is made once every 8 minutes;2.0345 ppm/step

#### [1] Default value.

For OFFM = 0, each LSB introduces an offset of 2.170 ppm. For OFFM = 1, each LSB introduces an offset of 2.0345 ppm. The offset value is coded in two's complement giving a range of +127 LSB to -128 LSB, see Table 24.

Table 24. Offset values

OFFSET[7:0]	Offset value in	Offset value in ppm				
	decimal	Normal mode OFFM = 0	Fast mode OFFM = 1			
011 1 1111	+127	+275.590	+258.3815			
011 1 1110	+126	+273.420	+256.3470			
:	:	:	:			
0000 0010	+2	+4.340	+4.0690			
0000 0001	+1	+2.170	+2.0345			
0000 0000 [1]	0	0 <sup>[1]</sup>	0 [1]			
1111 1111	-1	-2.170	-2.0345			
1111 1110	-2	-4.340	-4.0690			
:	÷	:	·			
1000 0001	-127	-275.590	-258.3815			
1000 0000	-128	-277.760	-260.416			

<sup>[1]</sup> Default value.

The correction is made by adding or subtracting clock correction pulses, thereby changing the period of a single second but not by changing the oscillator frequency.

It is possible to monitor when correction pulses are applied. See Section 7.8.4.

#### 7.8.1 Correction when OFFM = 0

The correction is triggered once every four hours and then correction pulses are applied once per minute until the programmed correction values have been implemented.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 25. Correction pulses for OFFM = 0

Correction value	Every n <sup>th</sup> hour	Actual minute
+1 or -1	4	00
+2 or -2	4	00 and 01
+3 or -3	4	00, 01, and 02
:	:	:
+59 or -59	4	00 to 58
+60 or -60	4	00 to 59
+61 or -61	4	00 to 59
	4 + 1	00
+62 or -62	4	00 to 59
	4 + 1	00 and 01
:	:	:
+123 or -123	4	00 to 59
	4 + 1	00 to 59
	4 + 2	00, 01, and 02
-128	4	00 to 59
	4 + 1	00 to 59
	4 + 2	00 to 07

## 7.8.2 Correction when OFFM = 1

The correction is triggered once every eight minutes and then correction pulses are applied once per second until the programmed correction values have been implemented.

Clock correction is made more frequently in OFFM = 1; however, this can result in higher power consumption.

Table 26. Correction pulses for OFFM = 1

Correction value	Every n <sup>th</sup> minute	Actual second	
+1 or -1	8	00	
+2 or -2	8	00 and 01	
+3 or -3	8	00, 01, and 02	
:	:	:	
+59 or -59	8	00 to 58	
+60 or -60	8	00 to 59	
+61 or -61	8	00 to 59	
	8 + 1	00	
+62 or -62	8	00 to 59	
	8 + 1	00 and 01	
:	:	:	


Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 26. Correction pulses for OFFM = 1...continued


Correction value	Every n <sup>th</sup> minute	Actual second	
+123 or -123	8	00 to 59	
	8 + 1	00 to 59	
	8 + 2	00, 01, and 02	
-128	8	00 to 59	
	8 + 1	00 to 59	
	8 + 2	00 to 07	

#### 7.8.3 Offset calibration workflow

The calibration offset has to be calculated based on the time. <u>Figure 20</u> shows the workflow how the offset register values can be calculated:



Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus



With the offset calibration an accuracy of  $\pm 1$  ppm (0.5 × offset per LSB) can be reached (see Table 24).

±1 ppm corresponds to a time deviation of 0.0864 seconds per day.

- 1. 4 correction pulses in OFFM = 0 correspond to -8.680 ppm.
- 2. 4 correction pulses in OFFM = 1 correspond to -8.138 ppm.
- 3. Reachable accuracy zone.

Figure 21. Result of offset calibration

#### 7.8.4 Offset interrupts

The generation of interrupts from the offset functions is controlled via the offset interrupt enable bits; OIEA and OIEB. These bits are in registers INTA\_enable (address 29h) and INTB enable (address 2Ah).

Every time a correction pulse is made an interrupt pulse can be generated at pins INTA and INTB. As there is no offset calibration flag, it is only possible to generate pulse interrupts.

See Section 7.9 for interrupt control.

### 7.9 Interrupts

There are two interrupt output pins,  $\overline{\text{INTA}}$  and  $\overline{\text{INTB}}$ . Both pins have the same possible sources and a dedicated register to control what is output. The pins can be used independently from each other.

INTA data is output on the INTA pin. INTA is an interrupt output pin with open-drain drive. INTA pin mode is controlled by INTAPM[1:0] bits in the Pin\_IO register (Section 7.12).

INTB data is output on TS pin with push-pull drive. The TS pin must first be configured as INTB output by setting TSIO[1:0] bits in the Pin\_IO register (Section 7.12).

Interrupts will only be output when the pin mode is correctly defined. Interrupts are output from the IC as active LOW signals.

The registers INTA\_enable (address 29h) and INTB\_enable (address 2Ah) are used to select which interrupts should be output on which pin.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 27. INTA and INTB interrupt control bits

Bit	7	6	5	4	3	2	1	0			
INTA_enable - INTA pin enable control (address 29h)											
Symbol	ILPA	PIEA	OIEA	A1IEA	A2IEA	TSRIEA	BSIEA	WDIEA			
INTB_ena	INTB_enable - INTB pin enable control (address 2Ah)										
Symbol	ILPB	PIEB	OIEB	A1IEB	A2IEB	TSRIEB	BSIEB	WDIEB			

Table 28. Definition of interrupt control bits

Bit	Symbol		Value	Description
	INTA	INTB		
7	ILPA	ILPB		level or pulse mode
			0 [1]	interrupt generates a pulse
			1	interrupt follows flags (permanent signal)
6	PIEA	PIEB		periodic interrupt enable
			0 [1]	no periodic interrupt generated
			1	periodic interrupt generated
5	OIEA	OIEB		offset correction interrupt enable
			0 [1]	no correction interrupt generated
			1	interrupt generated from correction
4	A1IEA	A1IEB		alarm1 interrupt enable
			0 [1]	no alarm interrupt generated
			1	alarm interrupt generated
3	A2IEA	A2IEB		alarm2 interrupt enable
			0 [1]	no alarm interrupt generated
			1	alarm interrupt generated
2	TSRIEA	TSRIEB		timestamp register interrupt enable
			0 [1]	no timestamp register interrupt generated
			1	timestamp register interrupt generated
1	BSIEA	BSIEB		battery switch interrupt enable
			0 [1]	no battery switch interrupt generated
			1	battery switch interrupt generated
0	WDIEA	WDIEB		WatchDog interrupt enable
			0 [1]	no WatchDog interrupt generated
			1	WatchDog interrupt generated

<sup>[1]</sup> Default value.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

## 7.9.1 ILPA/ILPB: interrupt level or pulse mode


Interrupts can be configured to generate a pulse or to send a continuous level (permanent signal) which follows the state of the flag.

In pulse mode, an interrupt pulse is generated every time that the selected source triggers.

#### Triggered means

- · for periodic interrupts, every time a period has elapsed
- · for offset correction, every time a correction pulse is initiated
- for alarms, every time the time increments to match the alarm time
- · for timestamps, every time a register updates
- for battery switch, every time the IC switches to or from battery
- for WatchDog, every time the counter reaches the end of its count

The interrupt signal goes active coincident with the triggering event. The signal is cleared by an internal 128 Hz clock. The internal clock is asynchronous to the triggering event and so the pulse duration has a minimum period of one 128 Hz cycle and a maximum of two 128 Hz cycles. Interrupt pulses may be shortened by clearing the flag before the end of the pulse period.




In level mode, the interrupt signal follows the state of the flag. Only interrupts which are enabled will affect the pin state. All enabled flags must be cleared for the interrupt signal to be cleared.

The EMON is used only for monitoring **all** flags and can be read back in the minutes register. See Section 7.2.3.

#### 7.9.2 Interrupt enable bits

The remainder of the bits in register INTA\_enable (address 29h) and register INTB\_enable (address 2Ah) are used to select which interrupt data goes where. See <a href="Figure 23">Figure 23</a>

# Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus



PCF85263A

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

## 7.10 Oscillator register

Table 29. Oscillator - oscillator control register (address 25h) bit description

			,					
Bit	7	6	5	4	3	2	1	0
Symbol	CLKIV	OFFM	12_24	LOWJ	OSCI	D[1:0]	CL[	1:0]
Section	Section 7.16	Section 7.8	<u>Section 7.10.3</u>	Section 7.10.4	Section	7.10.5	Section	7.10.6

### 7.10.1 CLKIV: invert the clock output

Table 30. CLKIV bit - oscillator control register (address 25h)

Bit	Symbol	Value	Description
7	CLKIV		output clock inversion
		0 [1]	non-inverting; LOWJ mode will affect rising edge
		1	inverted; LOWJ mode will affect falling edge

<sup>[1]</sup> Default value.

The clock selected with the COF[2:0] bits (register Function, address 28h) can be inverted. This is intended for use in conjunction with the low jitter mode, LOWJ. The low jitter mode reduces the jitter for the rising edge of the output clock. If the reduced jitter needs to be on the falling edge, for example when using an open-drain clock output, then the CLKIV bit can be used to implement this.

### 7.10.2 OFFM: offset calibration mode

See Section 7.8 for a full description of offset calibration.

### 7.10.3 12\_24: 12 hour or 24 hour clock

Table 31. 12\_24 bit - oscillator control register (address 25h)

Bit	Symbol	Value	Description		
5	12_24		12 hour or 24 hour mode		
		0 [1]	24 hour mode is selected		
		1	12 hour mode is selected		

<sup>[1]</sup> Default value.

In RTC mode, time counting can be configured for 24 hour clock or 12 hour clock with the AMPM flag.

This bit is ignored in stop-watch mode.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

## 7.10.4 LOWJ: low jitter mode

Table 32. LOWJ bit - oscillator control register (address 25h)

Bit	Symbol	Value	Description
4	LOWJ		low jitter CLK output bit
		0 <sup>[1]</sup>	normal
		1	reduced CLK output jitter; increase I <sub>DD</sub>

<sup>[1]</sup> Default value.

Oscillator circuits suffer from jitter. In particular, ultra low-power oscillators like the one used in the PCF85263A are optimized for power and not jitter. By setting the LOWJ bit, the jitter performance can be improved at the cost of power consumption.

### 7.10.5 OSCD[1:0]: quartz oscillator drive control

Table 33. OSCD[1:0] bits - oscillator control register (address 25h)

			<u> </u>
Bit	Symbol	Value	Description
3 to 2	OSCD[1:0]		oscillator drive bits
		00 [1]	normal drive; R <sub>S(max)</sub> : 100 kΩ
		01	low drive; $R_{S(max)}$ : 60 k $\Omega$ ; reduced $I_{DD}$
		10, 11	high drive; $R_{S(max)}$ : 500 kΩ; increased $I_{DD}$

<sup>[1]</sup> Default value.

The oscillator is designed to be used with quartz with a series resistance up to 100 k $\Omega$ . This covers the typical range of 32.768 kHz quartz crystals. Series resistance is also referred to as: ESR, motional resistance, or R<sub>S</sub>.

A low drive mode is available for low series resistance quartz. This reduces the current consumption.

For very high series resistance quartz, there is a high drive mode. Current consumption increases substantially in this mode.

## 7.10.6 CL[1:0]: quartz oscillator load capacitance

Table 34. CL[1:0] bits - oscillator control register (address 25h)

Bit	Symbol	Value	Description
1 to 0	CL[1:0]		internal oscillator capacitor selection for quartz crystals with the corresponding load capacitance of $C_L$ :
		00 [1]	7.0 pF
		01	6.0 pF
		10	12.5 pF
		11	12.5 pF

<sup>[1]</sup> Default value.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

 $C_L$  refers to the load capacitance of the oscillator circuit and allows for a certain amount of package and PCB parasitic capacitance. When the oscillator circuit matches the  $C_L$  parameter of the quartz, then the frequency offset is zero.

The PCF85263A is designed to operate with quartz with  $C_L$  values of 6.0 pF, 7.0 pF and 12.5 pF.

12.5 pF are generally the cheapest and most widely available, but also require the most power to drive. The circuit also operates with 9.0 pF quartz, however the offset calibration would be needed to compensate. If a 9.0 pF quartz is used, then it is recommended to set  $C_L$  to 7.0 pF.

# 7.11 Battery switch register

This register configures the battery switch-over mode.

Associated with the battery switch-over is the battery switch flag (BSF) in the Flags register (Section 7.14). Whenever the IC switches to battery operation, the flag is set. The flag can only be read when operating from  $V_{DD}$  power, however an interrupt pulse or static LOW signal can be generated whenever switching to battery. An interrupt pulse can also be generated when switching back to  $V_{DD}$  power. Examples are given in Figure 25 and Figure 26.

When switched to battery, the  $V_{DD}$  power domain is disabled. This means that  $I^2C$  pins are ignored, CLK output is disabled and Hi-Z, TS pin output mode is disabled and Hi-Z, TS digital input is ignored and may be left floating. TS pin mechanical switch detector is active.  $\overline{INTA}$  output is still active for interrupt output and battery switch indication, but disabled for clock output.

Table 35. IO pin behavior in battery mode

IO pin (mode)	V <sub>DD</sub> operation	V <sub>BAT</sub> operation
SCL	active input	disabled; may be left floating
SDA	active input/output	disabled; may be left floating
CLK	active output	disabled; Hi-Z
TS (output mode)	active output	disabled; Hi-Z
TS (digital input)	active input	disabled; may be left floating
TS (mechanical switch input)	active input	active input
INTA	active output	active interrupt output

Table 36. Battery\_switch - battery switch control (address 26h) bit description

Bit	7	6	5	4	3	2	1	0
Symbol	-	-	-	BSOFF	BSRR	BSM	[1:0]	BSTH
Section	-	-	-	<u>Section 7.11.1</u>	<u>Section 7.11.2</u>	Section	7.11.3	<u>Section 7.11.4</u>

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

## 7.11.1 BSOFF: battery switch on/off control

Table 37. BSOFF bit - battery switch control (address 26h) bit description

Bit	Symbol	Value	Description
4	BSOFF		battery switch on/off
		0 <sup>[1]</sup>	enable battery switch feature
		1	disable battery switch feature

<sup>[1]</sup> Default value.

The battery switch circuit may be disabled when not used. This disables all the circuit and save power consumption. When disabled connect  $V_{BAT}$  and  $V_{DD}$  together.

### 7.11.2 BSRR: battery switch internal refresh rate

Table 38. BSRR bit - battery switch control (address 26h) bit description

Bit	Symbol	Value	Description
3	BSRR		battery switch refresh rate
		0 [1]	low
		1	high

<sup>[1]</sup> Default value.

Non-user bit. Recommended to leave set at default.

### 7.11.3 BSM[1:0]: battery switch mode

Table 39. BSM[1:0] bits - battery switch control (address 26h) bit description

Bit	Symbol	Value	Description
2 to 1	BSM[1:0]		battery switch mode bits
		00 <sup>[1]</sup>	switching at the V <sub>th</sub> level
		01	switching at the V <sub>BAT</sub> level
		10	switching at the higher level of $V_{th}$ or $V_{BAT}$
		11	switching at the lower level of $V_{th}$ or $V_{BAT}$

<sup>[1]</sup> Default value.

Switching is automatic and controlled by the voltages on the VBAT and VDD pins. There are three modes:

- Compare V<sub>DD</sub> with an internal reference (V<sub>th</sub>)
- Compare V<sub>DD</sub> with V<sub>BAT</sub>
- Compare V<sub>DD</sub> with an internal reference (V<sub>th</sub>) and V<sub>BAT</sub>


The last mode is useful when a rechargeable battery is employed.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 40. Battery switch-over modes


BSM[1:0]	Condition	Internal power
00	$V_{DD} > V_{th}$	$V_{DD}$
	$V_{DD} < V_{th}$	$V_{BAT}$
01	$V_{DD} > V_{BAT}$	$V_{DD}$
	$V_{DD} < V_{BAT}$	$V_{BAT}$
10	V <sub>DD</sub> > the higher of V <sub>th</sub> or V <sub>BAT</sub>	$V_{DD}$
	$V_{DD}$ < the higher of $V_{th}$ or $V_{BAT}$	$V_{BAT}$
11	$V_{DD}$ > the lower of $V_{th}$ or $V_{BAT}$	$V_{DD}$
	V <sub>DD</sub> < the lower of V <sub>th</sub> or V <sub>BAT</sub>	$V_{BAT}$

Due to the nature of the power switch circuit there is a switching hysteresis (see <u>Figure 24</u> and <u>Table 67</u>).




Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

# 7.11.3.1 Switching at the $V_{th}$ level, BSM[1:0] = 00




7.11.3.2 Switching at the  $V_{BAT}$  level, BSM[1:0] = 01



Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

### 7.11.3.3 Switching at the higher of $V_{BAT}$ or $V_{th}$ level, BSM[1:0] = 10


With this mode switching takes place when  $V_{DD}$  falls below the higher of  $V_{th}$  or  $V_{BAT}$ . In Figure 27, an example is given where the threshold is set to 1.5 V and a single cell battery is connected to VBAT. In this example, switching to the battery voltage takes place when  $V_{DD}$  falls below  $V_{th}$ .



# 7.11.3.4 Switching at the lower of $V_{BAT}$ and $V_{th}$ level, BSM[1:0] = 11

With this mode switching takes place when  $V_{DD}$  falls below the lower of  $V_{th}$  or  $V_{BAT}$ . In <u>Figure 28</u>, an example is given where the threshold is set to 1.5 V and a single cell battery is connected to VBAT. In this example, switching to the battery voltage takes place when  $V_{DD}$  falls below  $V_{BAT}$ .

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus



### 7.11.4 BSTH: threshold voltage control

Table 41. BSTH - battery switch control (address 26h) bit description

Bit	Symbol	Value	Description
0	BSTH		battery switch threshold voltage, $V_{th}$
		0 <sup>[1]</sup>	V <sub>th</sub> = 1.5 V
		1	V <sub>th</sub> = 2.8 V

<sup>[1]</sup> Default value.

The threshold for battery switch-over is selectable between two voltages, 1.5 V and 2.8 V.

## 7.11.5 Battery switch interrupts

The generation of interrupts from the battery switch function is controlled via the battery switch interrupt enable bits; BSIEA and BSIEB. These bits are in registers INTA\_enable (address 29h) and INTB\_enable (address 2Ah).

The assertion of the flag BSF (register Flags, address 2Bh) can be used to generate an interrupt at pins  $\overline{\text{INTA}}$  and  $\overline{\text{INTB}}$ . The interrupt may be generated as a pulsed signal or alternatively as a permanently active signal which follows the condition of bit BSF. BSF remains set until cleared by command.

When enabled, interrupts are triggered every time the battery switch circuit switches to either battery or to  $V_{DD}$  and even if the BSF is not cleared, an interrupt pulse can be generated.

In addition, the INTA pin can be configured as a battery mode indicator (INTAPM[1:0] = 00). See <u>Section 7.12.6</u>. This mode differs from a general interrupt signal in that it is only controlled by the current battery switch status.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

See Section 7.9 for interrupt control.

**Remark:** INTB pin is only active when the IC is operating from V<sub>DD</sub>.

# 7.12 Pin\_IO register

Table 42. Pin\_IO- pin input output control register (address 27h) bit description

Bit	7	6	5	4	3	2	1	0
Symbol	CLKPM	TSPULL	TSL	TSIM	TSPN	<b>/</b> [1:0]	INTAP	M[1:0]
Section	<u>Section 7.12.1</u>	<u>Section 7.12.2</u>	Section 7.12.3	<u>Section 7.12.5</u>	Section	7.12.4	Section	7.12.6

This register is used to define the input and output modes of the IC.

## 7.12.1 CLKPM: CLK pin mode control

Table 43. CLKPM bit - Pin\_IO control register (address 27h)

Bit	Symbol	Value	Description
7	CLKPM [1]		CLK pin mode
		0 [2]	enable CLK pin
		1	disable CLK pin

<sup>[1]</sup> CLK pin is not available on all package types.

Setting the CLKPM bit disables the CLK output and force the pin to drive out a logic 0. Clearing this bit enables the pad to output the selected clock frequency (see bits COF[2:0] in the Function register, see <u>Table 50</u>).

### 7.12.2 TSPULL: TS pin pull-up resistor value

Table 44. TSPULL bit - Pin\_IO control register (address 27h)

Bit	Symbol	Value	Description
6	TSPULL		TS pin pull-up resistor value
		0 [1]	80 kΩ
		1	40 kΩ

<sup>[1]</sup> Default value.

Controls the pull-up resistor value used in the mechanical switch detector. For applications where there is a large capacitance on the TS pin e.g. from a long connecting cable to the mechanical switch, the pull-up resistor value can be halved to improve switch detection.

Using the low-resistance value increases current consumption when the switch is closed i.e. shorting to  $V_{\text{SS}}$ .

<sup>[2]</sup> Default value.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

## 7.12.3 TSL: TS pin level sense

Table 45. TSL bit - Pin\_IO control register (address 27h)

Bit	Symbol	Value	Description
5	TSL		TS pin input sense
		0 <sup>[1]</sup>	active HIGH
		1	active LOW

<sup>[1]</sup> Default value.

The active state of the TS pin can be defined for use as a timestamp trigger and/or as stop control for the time counting. Active HIGH implies a transition from logic 0 to logic 1 is active. Active LOW implies a transition from logic 1 to logic 0 is active.


### 7.12.4 TSPM[1:0]: TS pin I/O control

Table 46. TSPM[1:0] bits - Pin IO control register (address 27h)

Bit	Symbol	Value	Description
3 to 2	TSPM[1:0]		TS pin IO mode
		00 [1]	disabled; input can be left floating
		01	INTB output; push-pull
		10	CLK output; push-pull
		11	input mode

[1] Default value.

These bits control the operation of the TS pin.



TSIM is only considered when the TS pin is in input mode.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

### 7.12.4.1 TS pin output mode; INTB

It is possible to output  $\overline{\text{INTB}}$  data on the TS pin. The output is push-pull. No output is available when on  $V_{BAT}$ . When on  $V_{BAT}$  the output is Hi-Z.

### 7.12.4.2 TS pin output mode; CLK

It is possible to output a clock frequency on the TS pin. Clock frequency is selected with the COF[2:0] bits in the Function register (Section 7.13). The output is push-pull. No output is available when on  $V_{BAT}$ . When on  $V_{BAT}$  the output is Hi-Z.

#### 7.12.4.3 TS pin disabled

When disabled the pin is Hi-Z and can be left floating.

### 7.12.5 TSIM: TS pin input type control

Table 47. TSIM bit - Pin\_IO control register (address 27h)

Bit	Symbol	Value	Description
4	TSIM		TS pin input mode
		0 [1]	CMOS input; reference to $V_{DD}$ ; disabled when on $V_{BAT}$
		1	mechanical switch mode; active pull-up sampled at 16 Hz; operates on $V_{DD}$ and $V_{BAT}$

<sup>[1]</sup> Default value.

In CMOS input mode (TSIM = 0), input is taken directly from the TS pin. The input is conditioned by the setting of TSL. When operating on the battery voltage ( $V_{BAT}$ ), the input is disabled and is allowed to float.

In mechanical switch detector mode (TSIM = 1), the TS pin is sampled at a rate of 16 Hz for a period of 30.5  $\mu$ s. At the same time as the sample a pull-up resistor is activated to detect an open pin or a pin shorted to V<sub>SS</sub>. The input is referenced to the internal power supply. This mode operates when on V<sub>DD</sub> or V<sub>BAT</sub>. The pull-up resistor value can be controlled by TSPULL bit in the Pin\_IO register (see Section 7.12).

### 7.12.5.1 TS pin input mode

There are two input types which are controlled by the TSIM bit. The TS input can be used to generate a timestamp event by configuring the timestamp mode bits; TSR2M[2:0] and TSR1M[1:0] bits in TSR\_mode register (see <u>Table 19</u>).

Also it is possible to use the TS pin to control counting of time. This is typically for use with the stop-watch mode where an elapsed time counter function can be implemented. Using the STOPM bit in the Function register (see <u>Table 50</u>) it is possible to control the STOP bit by the TS pin.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus


## 7.12.6 INTAPM[1:0]: INTA pin mode control

Table 48. INTAPM[1:0] bits - Pin\_IO control register (address 27h)

Bit	Symbol	Value	Description
1 to 0	INTAPM[1:0]		INTA pin mode
		00 [1]	CLK output mode
		01	battery mode indication
		10	INTA output
		11	Hi-Z

[1] Default value.

The INTA pin can be used to output three different signals.



### 7.12.6.1 INTAPM[1:0]: INTA

The primary function of the INTA pin is to output INTA data. INTA data is controlled by the bits of the INTA\_enable register (see <u>Table 28</u>).

The output is active LOW with an open-drain output. The output is available during  $V_{DD}$  and  $V_{BAT}$  operation.

#### 7.12.6.2 INTAPM[1:0]: clock data

It is possible to output a clock frequency on the  $\overline{\text{INTA}}$  pin. Clock frequency is selected with the COF[2:0] bits in the Function register (Section 7.13). The output is active LOW with an open-drain output. The output is available only during  $V_{DD}$  operation. The output is Hi-Z when operating from  $V_{BAT}$ .

**Remark:** Clock output is the default state. To save power, it is recommended to disable the clock when not being used. If no clock is required, then set COF[2:0] in the Function register (Section 7.13) to CLK disabled. If clock output is only required on the CLK pin, then set the INTA pin to either INTA data or battery mode.

### 7.12.6.3 INTAPM[1:0]: battery mode indication

It is possible to output the state of the power switch on the  $\overline{\text{INTA}}$  pin. The output has an open-drain output. The output is available during  $V_{DD}$  and  $V_{BAT}$  operation.

Table 49. INTA battery mode

Power supply INTA pin state	
$V_{DD}$	ĪNTĀ = Hi-Z
$V_{BAT}$	INTA = logic 0

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

# 7.13 Function register

Table 50. Function - chip function control register (address 28h) bit description

Bit	7	6	5	4	3	2	1	0
Symbol	100TH	PI[	1:0]	RTCM	STOPM		COF[2:0]	
Section	<u>Section 7.13.1</u>	Section	7.13.2	<u>Section 7.13.3</u>	<u>Section 7.13.4</u>	<u>Se</u>	ection 7.13	<u>3.5</u>

#### 7.13.1 100TH: 100th seconds mode

Table 51. 100TH bit - Function control register (address 28h)

Bit	Symbol	Value	Description
7	100TH		100th second mode
		0 [1]	100th second disabled
		1	100th second enabled

<sup>[1]</sup> Default value.

The PCF85263A can be configured to count at a resolution of 1 second or 0.01 seconds. In 100th mode, the 100th\_seconds register becomes available and the RTC counts at a resolution of 0.01 seconds.

The 256 Hz clock signal is divided by 3 for fourteen 100 Hz periods and then by 2 for eleven 100 Hz periods. This produces an effective division ratio of 2.56 with a maximum jitter of 3.91 ms. Over twenty-five 100 Hz cycles the jitter is 0 ns.

### 7.13.2 PI[1:0]: Periodic interrupt

Table 52. PI[1:0] bits - Function control register (address 28h)

Bit	Symbol	Value	Description
6 to 5	PI[1:0]		periodic interrupt
		00 [1]	no periodic interrupt
		01	once per second
		10	once per minute
		11	once per hour

<sup>[1]</sup> Default value.

The periodic interrupt mode can be used to enable pre-defined timers for generating pulses on the interrupt pin. Interrupts once per second, once per minute or once per hour can be generated.

When disabled, the timers are reset. When enabled, the time to the first pulse is between the chosen period and the chosen period minus 1 seconds.

The timers are not affected by STOP.

When the periodic interrupt triggers, the PIF (PI flag) in the Flags register (Section 7.14) is set.

The flag does not have to be cleared to allow another INTA or INTB pulse.

The duration of the periodic interrupt is unaffected by offset calibration.

PCF85263A

All information provided in this document is subject to legal disclaimers.

© NXP B.V. 2021. All rights reserved.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

See Section 7.9 for a description of interrupt pulse control and output pins.

#### 7.13.3 RTCM: RTC mode

Table 53. RTCM bit - Function control register (address 28h)

Bit	Symbol	Value	Description
4	RTCM		RTC mode
		0 <sup>[1]</sup>	real-time clock mode
		1	stop-watch mode

<sup>[1]</sup> Default value.

The RTC mode is used to control how the time is counted. When configured as a classic RTC, then time is counted from 100th seconds to years. In stop-watch mode, time is counted from 100th seconds to 999 999 hours.

Table 54. RTC time counting modes

RTCM	Mode	Time counting
0	RTC	100th seconds <sup>[1]</sup> , seconds, minutes, hours, days, weekdays, months, years
1	stop-watch	100th seconds [1], seconds, minutes, hours (0 hours to 999 999 hours)

<sup>[1]</sup> Enabled with 100TH bit in the Function register (Section 7.13).

### 7.13.4 STOPM: STOP mode control

Table 55. STOPM bit - Function control register (address 28h)

Bit	Symbol	Value	Description
3	STOPM		STOP mode
		0 [1]	RTC stop is controlled by STOP bit only
		1	RTC stop is controlled by STOP bit or TS pin

<sup>[1]</sup> Default value.

The STOP register bit in the Oscillator register (Section 7.10) is used to stop the counting of time in both RTC mode and stop-watch mode. Stopping of the oscillator can also be controlled from the TS pin. The TS pin must first be configured as an input by the TSPM[1:0] bits, then selected for active HIGH or active LOW by the TSL bits.

Table 56. Oscillator stop control when STOPM = 1

STOP bit [1]	TSL	TS pin [2]	Oscillator state	Description
0	0	0	running	TS pin active HIGH
		1	stopped	
	1	0	stopped	TS pin active LOW
		1	running	
1	-	-	stopped	TS pin ignored

<sup>[1]</sup> In the Oscillator register (Section 7.10).

<sup>[2]</sup> TSPM[1:0] = 11.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

## 7.13.5 COF[2:0]: Clock output frequency

Table 57. COF[2:0] bits - Function control register (address 28h)

Bit	Symbol	Value	Frequency selection (Hz)				
			CLK pin	TS pin	INTA pin		
2 to 0	COF[2:0]	000 [1]	32 768	32 768	32 768		
		001	16 384	16 384	16 384		
		010	8 192	8 192	8 192		
		011	4 096	4 096	4 096		
		100	2 048	2 048	2 048		
		101	1 024	1 024	1 024		
	110	1	1	1			
		111	static LOW	static LOW	Hi-Z		

<sup>[1]</sup> Default value.

A programmable square wave is available at pin CLK. Operation is controlled by the COF[2:0] bits. Frequencies of 32.768 kHz (default) down to 1 Hz can be generated for use as a system clock, microcontroller clock, input to a charge pump, or for calibration of the oscillator.

Pin CLK is a push-pull output and enabled at power-on. Pin CLK can be disabled by setting CLKPM = 1 in the Pin\_IO register (<u>Section 7.12</u>). When disabled, the CLK pin is LOW.

The selected clock frequency may also be output on the TS pin and the INTA pin. The CLKIV bit may be used to invert the clock output. CLKIV does not invert for the setting COF[2:0] = 111.

The duty cycle of the selected clock is not controlled. However, due to the nature of the clock generation, all clock frequencies except 32.768 kHz have a duty cycle of 50:50.

Table 58. Clock duty cycles

COF[2:0]	Frequency (Hz)	Typical duty cycle <sup>[1]</sup>
000 [2]	32 768	60 : 40 to 40 : 60
001	16 384	50 : 50
010	8 192	50 : 50
011	4 096	50 : 50
100	2 048	50 : 50
101	1 024	50 : 50
110	1 <sup>[3]</sup>	50 : 50
111	static	-

<sup>[1]</sup> Duty cycle definition: % HIGH-level time : % LOW-level time.

<sup>[2]</sup> Default values. The duty cycle of the CLKOUT when outputting 32,768 Hz could change from 60:40 to 40:60 depending on the detector since the 32,768 Hz is derived from the oscillator output which is not perfect. It could change from device to device and it depends on the silicon diffusion. There is nothing that can be done from outside the chip to influence the duty cycle.

<sup>[3] 1</sup> Hz clock pulses are not affected by offset correction pulses.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

# 7.14 Flags register

Table 59. Flags - Flag status register (address 2Bh) bit description

Bit	Symbol	Flag name	Value	Description
7	PIF	Periodic Interrupt Flag	0 [1]	read: periodic interrupt flag inactive
		<u>Section 7.13.2</u>		write: periodic interrupt flag is cleared
			1	read: periodic interrupt flag active
				write: periodic interrupt flag remains unchanged
6	A2F	Alarm2 Flag	0 [1]	read: alarm2 flag inactive
		Section 7.4		write: alarm2 flag is cleared
			1	read: alarm2 flag active
				write: alarm2 flag remains unchanged
5	A1F	Alarm1 Flag	0 [1]	read: alarm1 flag inactive
		Section 7.4		write: alarm1 flag is cleared
			1	read: alarm1 flag active
				write: alarm1 flag remains unchanged
4	WDF	WatchDog Flag	0 [1]	read: WatchDog flag inactive
		Section 7.5		write: WatchDog flag is cleared
			1	read: WatchDog flag active
				write: WatchDog flag remains unchanged
3	BSF	Battery Switch Flag	0 [1]	read: battery switch flag inactive
		Section 7.11		write: battery switch flag is cleared
			1	read: battery switch flag active
				write: battery switch flag remains unchanged
2	TSR3F	Timestamp Register 3	0 [1]	read: timestamp register 3 flag inactive
		event Flag Section 7.7		write: timestamp register 3 flag is cleared
			1	read: timestamp register 3 flag active
				write: timestamp register 3 flag remains unchanged
1	TSR2F	Timestamp Register 2	0 <sup>[1]</sup>	read: timestamp register 2 flag inactive
		event Flag Section 7.7		write: timestamp register 2 flag is cleared
	<u> </u>		1	read: timestamp register 2 flag active
				write: timestamp register 2 flag remains unchanged
0	TSR1F	Timestamp Register 1	0 [1]	read: timestamp register 1 flag inactive
		event Flag Section 7.7		write: timestamp register 1 flag is cleared
		233311111	1	read: timestamp register 1 flag active
				write: timestamp register 1 flag remains unchanged

<sup>[1]</sup> Default value.

The flags are set by their respective function. A full description can be found there. All flags behave the same way. They are set by some function of the IC and remain set until

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

overwritten by command. It is possible to clear flags individually. To prevent one flag being overwritten while clearing another, a logic AND is performed during a write access. All flags are combined to generate an event monitoring signal called EMON. EMON is described in <u>Section 7.2.3</u> and can be read as the MSB of minutes register.

### 7.15 Reset register

Table 60. Reset - software reset control (address 2Fh) bit description

Bit	7	6	5	4	3	2	1	0
Symbol	CPR	0	1	0	SR	1	0	CTS
Section	<u>Section 7.15.2</u>				Section 7.15.1			<u>Section 7.15.3</u>

#### For a


- software reset (SR), 0010 1100 (2Ch) must be sent to register Reset (address 2Fh). A software reset also triggers CPR and CTS
- clear prescaler (CPR), 1010 0100 (A4h) must be sent to register Reset (address 2Fh)
- clear timestamp (CTS),0010 0101 (25h) must be sent to register Reset (address 2Fh)

It is possible to combine CPR and CTS by sending 1010 0101 (A5h).

Remark: Any other value sent to this register is ignored.

#### 7.15.1 SR - Software reset

A reset is automatically generated at power-on. A reset can also be initiated with the software reset command.



The PCF85263A resets to:

Mode: real-time clock, 100th second off

Time: 00:00:00.00

Date: 2000.01.01

Weekday: Saturday

Battery switch: on, switching on the lower threshold voltage

Oscillator: C<sub>L</sub> = 7 pF

**Pins**:  $\overline{\text{INTA}}$  = 32 kHz output, CLK = 32 kHz output, TS = disabled

PCF85263A

All information provided in this document is subject to legal disclaimers.

© NXP B.V. 2021. All rights reserved

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

In the reset state, all registers are set according to <u>Table 61</u>.

Table 61. Registers reset values
Registers labeled as - remain unchanged.

Address	Register name	Bit							
		7	6	5	4	3	2	1	0
00h	100TH_seconds	0	0	0	0	0	0	0	0
01h	Seconds	1	0	0	0	0	0	0	0
02h	Minutes	0	0	0	0	0	0	0	0
03h	Hours	0	0	0	0	0	0	0	0
04h	Days	0	0	0	0	0	0	0	1
05h	Weekdays	0	0	0	0	0	1	1	0
06h	Months	0	0	0	0	0	0	0	1
07h	Years	0	0	0	0	0	0	0	0
08h	Second_alarm1	-	-	-	-	-	-	-	-
	Second_alm1								
09h	Minute_alarm1	-	-	-	-	-	-	-	-
	Minute_alm1								
0Ah	Hour_alarm1	-	-	-	-	-	-	-	-
	Hr_xx_xx_00_alm1								
0Bh	Day_alarm1	-	-	-	-	-	-	-	-
	Hr_xx_00_xx_alm1								
0Ch	Month_alarm1		-	-	-	-	-	-	-
	Hr_00_xx_xx_alm1								
0Dh	Minute_alarm2		-	-	-	-	-	-	-
	Minute_alm2								
0Eh	Hour_alarm2	-	-	-	-	-	-	-	-
	Hr_xx_00_alm2								
0Fh	Weekday_alarm2	-	-	-	-	-	-	-	-
	Hr_00_xx_alm2								
10h	Alarm enables	0	0	0	0	0	0	0	0
11h to 16h	Timestamp 1	0	0	0	0	0	0	0	0
17h to 1Ch	Timestamp 2	0	0	0	0	0	0	0	0
1Dh to 22h	Timestamp 3	0	0	0	0	0	0	0	0
23h	Timestamp_mode	0	0	0	0	0	0	0	0
24h	Offset	0	0	0	0	0	0	0	0
25h	Oscillator	0	0	0	0	0	0	0	0
26h	Battery_switch	0	0	0	0	0	0	0	0
27h	Pin_IO	0	0	0	0	0	0	0	0

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 61. Registers reset values...continued Registers labeled as - remain unchanged.

Address	Register name	Bit	Bit							
		7	6	5	4	3	2	1	0	
28h	Function	0	0	0	0	0	0	0	0	
29h	INTA_enable	0	0	0	0	0	0	0	0	
2Ah	INTB_enable	0	0	0	0	0	0	0	0	
2Bh	Flags	0	0	0	0	0	0	0	0	
2Ch	RAM_byte	0	0	0	0	0	0	0	0	
2Dh	WatchDog	0	0	0	0	0	0	0	0	
2Fh	Reset	0	0	0	0	0	0	0	0	

### 7.15.2 CPR: clear prescaler

To set the time for RTC mode accurately or to clear the time in stop-watch mode, the clear prescaler instruction is needed.

Before sending this instruction, it is recommended to first set *stop* either by the STOP bit or by the TS pin (see STOPM bit).

See STOP definition for an explanation on using this instruction.

## 7.15.3 CTS: clear timestamp

The timestamp registers (address 11h to 22h) can be set to all 0 with this instruction.

### 7.16 Stop\_enable register

Table 62. Stop\_enable - control of STOP bit (address 2Eh)

Bit	Symbol	Value	Description	
7 to 1	-	0000 000	not used	
0	STOP		STOP bit	
		0 <sup>[1]</sup>	RTC clock runs	
		1	RTC clock is stopped	

<sup>[1]</sup> Default value

The STOP bit stops the time from counting in both RTC mode and stop-watch mode. For RTC mode STOP is useful to set the time accurately. For stop-watch mode it is the start/stop control for the watch.


The counter can also be controlled from the TS pin by configuring STOPM in the Function register (Section 7.13). The internal *stop* signal is a combination of STOP and the TS pin state.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 63. Counter stop signal

STOP bit	STOP bit TS pin [1] [2]		Counter
1	-	1	stopped
-	1	1	stopped
0	0	0	running

- [1] Requires STOPM and TSPM[1:0] to be configured.
- [2] TSL = 0 (active HIGH) (Pin\_IO register, address 27h).




The *stop* signal blocks the 8.192 kHz clock from generating system clocks and freezes the time. In this state, the prescaler can be cleared with the CPR command in the Resets register (Section 7.15).

Remark: The output of clock frequencies is not affected.

The time circuits can then be set and do not increment until the STOP bit is released.

The *stop* acts on the 8.192 kHz signal. And because the I<sup>2</sup>C-bus or TS pin input is asynchronous to the crystal oscillator, the accuracy of restarting the time circuits is between zero and one 8.192 kHz cycle (see <u>Figure 33</u>).



The first increment of the time circuits is between 0 s and 122 µs after STOP is released.

The flow for accurately setting the time in RTC mode is:

- start an I<sup>2</sup>C access at register 2Eh
- set STOP bit
- · send CPR instruction
- · address counter rolls over to address 00h
- set time (100th seconds, seconds to years)

PCF85263A

All information provided in this document is subject to legal disclaimers.

© NXP B.V. 2021. All rights reserved

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

- end I<sup>2</sup>C access
- · wait for external time reference to indicate that time counting should start
- start an I<sup>2</sup>C access at register 2Eh
- clear STOP bit (time starts counting from now)
- end I<sup>2</sup>C access


The flow for resetting time in stop-watch mode is:

- start an I<sup>2</sup>C access at register 2Eh
- set STOP bit
- · send CPR instruction
- · address counter will roll over to address 00h
- set time to 000000:00:00.00
- end I<sup>2</sup>C access


# 8 I<sup>2</sup>C-bus interface

The I<sup>2</sup>C-bus is for bidirectional, two-line communication between different ICs. The two lines are a Serial DAta line (SDA) and a Serial CLock line (SCL). Both lines must be connected to a positive supply via a pull-up resistor. Data transfer may be initiated only when the bus is not busy. Both data and clock lines remain HIGH when the bus is not busy. The PCF85263A acts as a target receiver when being written to and as a target transmitter when being read from.

**Remark:** When on V<sub>BAT</sub> power, the interface is not accessible.



Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus



### 8.1 Bit transfer

One data bit is transferred during each clock pulse. The data on the SDA line must remain stable during the HIGH period of the clock pulse, as changes in the data line at this time are interpreted as STOP or START conditions.

### 8.2 START and STOP conditions

A HIGH-to-LOW transition of the data line while the clock is HIGH is defined as the START condition - S.

A LOW-to-HIGH transition of the data line while the clock is HIGH is defined as the STOP condition - P (see Figure 35).

### 8.3 Acknowledge

Each byte of 8 bits is followed by an acknowledge cycle. An acknowledge is defined as logic 0. A not-acknowledge is defined as logic 1.

When written to, the target will generate an acknowledge after the reception of each byte. After the acknowledge, another byte may be transmitted. It is also possible to send a STOP or START condition.

When read from, the controller receiver must generate an acknowledge after the reception of each byte. When the controller receiver no longer requires bytes to be transmitter, it must generate a not-acknowledge. After the not-acknowledge, either a STOP or START condition must be sent.

A detailed description of the I<sup>2</sup>C-bus specification is given in [8].

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

# 9 Interface protocol

The PCF85263A uses the I<sup>2</sup>C interface for data transfer. Interpretation of the data is determined by the interface protocol.

# 9.1 Write protocol

After the I<sup>2</sup>C target address is transmitted, the PCF85263A requires that the register address pointer is defined. It can take the value 00h to 2Fh. Values outside of that range will result in the transfer being ignored, however the target will still respond with acknowledge pulses.

After the register address is transmitted, write data is transmitted. The minimum number of data write bytes is 0 and the maximum number is unlimited. After each write, the address pointer increments by one. After address 2Fh, the address pointer will roll over to 00h.

- I<sup>2</sup>C START condition
- I<sup>2</sup>C target address + write
- · register address
- · write data
- · write data
- :
- · write data
- I<sup>2</sup>C STOP condition; an I<sup>2</sup>C RE-START condition is also possible.

### 9.2 Read protocol

When reading the PCF85263A, reading starts at the current position of the address pointer. The address pointer for read data should first be defined by a write sequence.

- I<sup>2</sup>C START condition
- I<sup>2</sup>C target address + write
- register address
- I<sup>2</sup>C STOP condition; an I<sup>2</sup>C RE-START condition is also possible.

After setting the address pointer, a read can be executed. After the I<sup>2</sup>C target address is transmitted, the PCF85263A will immediately output read data. After each read, the address pointer increments by one. After address 2Fh, the address pointer will roll over to 00h.

- I<sup>2</sup>C START condition
- I<sup>2</sup>C target address + read
- read data (controller sends acknowledge bit)
- read data (controller sends acknowledge bit)
- •
- read data (controller sends not-acknowledge bit)
- I<sup>2</sup>C STOP condition. An I<sup>2</sup>C RE-START condition is also possible.

The controller must indicate that the last byte has been read by generating a not-acknowledge after the last read byte.

PCF85263A

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

# 9.3 Target addressing

### 9.3.1 Target address

One I<sup>2</sup>C-bus target address (1010 001) is reserved for the PCF85263A. The entire I<sup>2</sup>C-bus target address byte is shown in <u>Table 64</u>.

Table 64. I<sup>2</sup>C target address byte

	Target address							
Bit	7	6	5	4	3	2	1	0
	MSB							LSB
	1	0	1	0	0	0	1	R/W

After a START condition, the I<sup>2</sup>C target address has to be sent to the PCF85263A device.


Target address can also be written in a hexadecimal format:

- A2h Write target address
- · A3h Read target address

# 10 Application design-in information

In this application, stop-watch mode is used to implement an elapsed time counter. The TS pin is used with a mechanical switch to start and stop the time. Each time the time is stopped, timestamp2 is loaded with the current time and an interrupt is generated on the  $\overline{\text{INTA}}$  pin.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus



The RTC must be configured correctly for this mode of operation. Outlined in <u>Table 65</u> are the settings needed for this mode.

In addition, the time must be set and any other configurations like battery switch-over, quartz oscillator driving mode, etc., which are dependent on the application.


The sampler circuit shown in Figure 36 will hold invalid data until the mechanical switch detector mode is enabled. It then requires a minimum of one sample period to initialize to the current TS pin level. It is recommended to enable the mechanical detector mode on the TS pin at least 62.5 ms before enabling the TS event mode. Failure to do so can result in a false first event.

Table 65. Application configuration

Register	Section	Bit(s)	State	Comment
Pin_IO	Section 7.12	TSPM[1:0]	11	TS pin in input mode
Pin_IO	Section 7.12	TSIM	1	select mechanical switch mode
Pin_IO	Section 7.12	TSL	1	TS pin input is active LOW
Function	Section 7.13	STOPM	1	allow TS pin to control STOP
		TSRIEA	1	allow timestamps to create interrupts
		ILPA	0	generate interrupt pulses
TSR_mode	Section 7.12	TSR2M[2:0]	101	last event mode for timestamp2
Pin_IO	Section 7.12	INTAPM[1:0]	10	output interrupt on INTA

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus


<u>Figure 37</u> shows the waveforms that can be expected. *sample clock*,  $vdd\_int$  and stop are internal nodes.  $vdd\_int$  is the supply which operates the IC and will be either  $V_{DD}$  or  $V_{BAT}$ , depending on the state of the battery switch-over.



- At and before t1, SW1 is open (TS pin floating). The TS pin is sampled and the internal pull-up resistor will pull the pin HIGH to *vdd\_int*. No actions are taken by the IC.
- At t2, SW1 is still open. No action is taken by the IC.
- At t3, SW1 closes. The TS pin is now shorted to V<sub>SS</sub>. The TS pin has not been sampled yet, so no action is taken by the IC.
- At t4, SW1 is closed. The internal pull-up resistor is enabled, but TS pin remains LOW. The pin is then sampled and the LOW level detected. As the TSL bit was set for active LOW detection, the HIGH-LOW transition of TS pin sampled triggers an event. STOPM mode was configured to allow the TS pin to stop the time counting. As the TSL bit was set for active LOW, time counting stops when the TS pin is LOW. Timestamp register 2 was configured to take a copy of the time on an event of the TS pin, hence TSR2 loads the time t4. TSR2F is also set.
  INTA was configured to generate an interrupt when TSR2 loads a new time, hence an interrupt pulse is seen on INTA.
- At t5, SW1 is opened. No action is taken by the IC.
- At t6, SW1 is open. The internal pull-up is active and the TS pin raises to vdd\_int level.
  The HIGH level is sampled and causes the stop signal to be released and time starts
  counting again.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

# 11 Internal circuitry



# 12 Safety notes

### **CAUTION**



This device is sensitive to ElectroStatic Discharge (ESD). Observe precautions for handling electrostatic sensitive devices.

Such precautions are described in the ANSI/ESD S20.20, IEC/ST 61340-5, JESD625-A or equivalent standards.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

# 13 Limiting values

Table 66. Limiting values

In accordance with the Absolute Maximum Rating System (IEC 60134).

Symbol	Parameter	Conditions		Min	Max	Unit
V <sub>DD</sub>	supply voltage			-0.5	+6.5	V
I <sub>DD</sub>	supply current			-50	+50	mA
$V_{BAT}$	battery supply voltage			-0.5	+6.5	V
I <sub>BAT</sub>	battery supply current			-50	+50	mA
VI	input voltage	on pins SCL, SDA, OSCI, TS		-0.5	+6.5	V
Vo	output voltage			-0.5	+6.5	V
I <sub>I</sub>	input current	at any input		-10	+10	mA
Io	output current	at any output		-10	+10	mA
P <sub>tot</sub>	total power dissipation			-	300	mW
V <sub>ESD</sub>	electrostatic discharge voltage	НВМ	[1]	-	±3500	V
		CDM	[2]			
		PCF85263AT		-	±1500	V
		PCF85263ATL		-	±1750	V
		PCF85263ATT		-	±1000	V
		PCF85263ATT1		-	±2000	V
		PCF85263AUK		-	±1000	V
I <sub>lu</sub>	latch-up current		[3]	-	200	mA
T <sub>stg</sub>	storage temperature		[4]	-65	+150	°C
T <sub>amb</sub>	ambient temperature	operating device		-40	+85	°C

Pass level; Human Body Model (HBM) according to [1].

# 14 Characteristics

Table 67. Characteristics

 $V_{DD}$  = 0.9 V to 5.5 V;  $V_{SS}$  = 0 V;  $T_{amb}$  = -40 °C to +85 °C;  $f_{osc}$  = 32.768 kHz; quartz  $R_s$  = 60 k $\Omega$ ;  $C_L$  = 7 pF; all registers in reset state; unless otherwise specified.

Symbol	Parameter	Conditions		Min	Тур	Max	Unit
Supplies							
$V_{DD}$	supply voltage	interface inactive; f <sub>SCL</sub> = 0 Hz	[1]	0.9	-	5.5	V
		interface active; f <sub>SCL</sub> = 400 kHz	[2]	1.8	-	5.5	V
V <sub>BAT</sub>	battery supply voltage		[1]	0.9	-	5.5	V

Pass level; Charged-Device Model (CDM), according to [2].

Pass level; latch-up testing, according to [3] at maximum ambient temperature (T<sub>amb(max)</sub>).

According to the store and transport requirements (see [9]) the devices have to be stored at a temperature of +8 °C to +45 °C and a humidity of 25 % to

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 67. Characteristics...continued

 $V_{DD}$  = 0.9 V to 5.5 V;  $V_{SS}$  = 0 V;  $T_{amb}$  = -40 °C to +85 °C;  $f_{osc}$  = 32.768 kHz; quartz  $R_s$  = 60 k $\Omega$ ;  $C_L$  = 7 pF; all registers in reset state; unless otherwise specified.

Symbol	Parameter	Conditions		Min	Тур	Max	Unit
I <sub>DD</sub>	supply current	CLKOUT disabled; $V_{DD}$ = 3.3 V; interface inactive; $f_{SCL}$ = 0 Hz	[3]				
		battery switch enabled					
		T <sub>amb</sub> = 25 °C		-	320	480	nA
		T <sub>amb</sub> = 50 °C		-	370	550	nA
		T <sub>amb</sub> = 85 °C		-	590	885	nA
		battery switch disabled	[4]		-		_
		T <sub>amb</sub> = 25 °C		-	280	420	nA
		T <sub>amb</sub> = 50 °C		-	330	500	nA
		T <sub>amb</sub> = 85 °C		-	550	825	nA
		CLKOUT disabled; $V_{DD}$ = 3.3 V; interface active; $f_{SCL}$ = 400 kHz		-	10	-	μΑ
Reference	voltage			,	'	'	
$V_{th}$	threshold voltage	HIGH falling V <sub>DD</sub>		2.4	2.6	2.8	V
		HIGH rising V <sub>DD</sub>		2.5	2.7	2.95	V
		LOW falling V <sub>DD</sub>		1.3	1.4	1.5	V
		LOW rising V <sub>DD</sub>		1.37	1.47	1.6	V
		reference voltage hysteresis		-	±50	-	mV
Inputs <sup>[5]</sup>				J			
VI	input voltage			-0.5	-	+5.5	V
V <sub>IL</sub>	LOW-level input voltage			-0.5	-	+0.3V <sub>DD</sub>	V
V <sub>IH</sub>	HIGH-level input voltage			0.7V <sub>DD</sub>	-	5.5	V
l <sub>LI</sub>	input leakage current	$V_I = V_{SS}$ or $V_{DD}$		-	0	-	μA
		post ESD event		-0.5	-	+0.5	μA
C <sub>i</sub>	input capacitance		[6]	-	-	7	pF
R <sub>PU(TS)</sub>	pull-up resistance on	80 kΩ mode	[7]	68	80	92	kΩ
. ,	pin TS	40 kΩ mode	[7]	36	40	64	kΩ
Outputs		I		I.			
V <sub>OH</sub>	HIGH-level output voltage	on pin CLK, TS		0.8V <sub>DD</sub>	-	V <sub>DD</sub>	V
V <sub>OL</sub>	LOW-level output voltage	on pins SDA, INTA, CLK, TS		V <sub>SS</sub>	-	0.2V <sub>DD</sub>	V

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 67. Characteristics...continued

 $V_{DD}$  = 0.9 V to 5.5 V;  $V_{SS}$  = 0 V;  $T_{amb}$  = -40 °C to +85 °C;  $f_{osc}$  = 32.768 kHz; quartz  $R_s$  = 60 k $\Omega$ ;  $C_L$  = 7 pF; all registers in reset state; unless otherwise specified.

Symbol	Parameter	Conditions		Min	Тур	Max	Unit
I <sub>OH</sub>	HIGH-level output current	output source current; V <sub>OH</sub> = 2.9 V; V <sub>DD</sub> = 3.3 V; on pin CLK, TS		1	3	-	mA
l <sub>OL</sub>	LOW-level output current	output sink current; $V_{OL} = 0.4 \text{ V}$ ; $V_{DD} = 3.3 \text{ V}$					
		on pin SDA		3	8.5	-	mA
		on pin ĪNTA		2	6	-	mA
		on pin CLK		1	3	-	mA
		on pin TS		1	3	-	mA
Oscillator					<u> </u>		'
$\Delta f_{\rm osc}/f_{\rm osc}$	relative oscillator frequency variation	$\Delta V_{DD}$ = 200 mV; $T_{amb}$ = 25 °C		-	0.075	-	ppm
t <sub>jit</sub>	jitter time	LOWJ = 0	[8]	-	50	-	ns
		LOWJ = 1		-	25	-	ns
C <sub>L(itg)</sub>	integrated load capacitance	on pins OSCO, OSCI; V <sub>DD</sub> = 3.3 V	[9]				
		C <sub>L</sub> = 6 pF		4.8	6	7.2	pF
		C <sub>L</sub> = 7 pF		5.6	7	8.4	pF
		C <sub>L</sub> = 12.5 pF		10	12.5	15	pF
R <sub>s</sub>	series resistance	of the quartz; normal drive	[10]	-	60	100	kΩ

For reliable oscillator start-up at power-on use V<sub>DD</sub> greater than 1.2 V. If powered up at 0.9 V the oscillator will start but it might be a bit slow, especially if at high temperature. Normally the power supply is not 0.9 V at start-up and only comes at the end of battery discharge. VDD min of 0.9 V is specified so that the customer can calculate how large a battery or capacitor they need for their application. V<sub>DD</sub> min of 1.2 V or greater is needed to ensure speedy oscillator start-up time.

Measured after reset and CLK disabled, level of inputs is V<sub>DD</sub> or V<sub>SS</sub>.

[4] [5] The I<sup>2</sup>C-bus interface of PCF85263A is 5 V tolerant.

[6] [7] Implicit by design.

[8]

Integrated load capacitance,  $C_{L(itg)}$ , is a calculation of  $C_{OSCI}$  and  $C_{OSCO}$  in series.


$$C_{L(itg)} = \frac{(C_{OSCI}C_{OSCO})}{(C_{OSCI}+C_{OSCO})}$$

[10] See Table 33.

<sup>400</sup> kHz I2C operation is production tested at 1.8 V. Design methodology allows I2C operation at 1.8 V - 5 % (1.71 V) which has been verified during product characterization on a limited number of devices.

Measured after reset, CLK disabled, battery switch disabled and level of inputs is V<sub>DD</sub> or V<sub>SS</sub>.


Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus



T<sub>amb</sub> = 25 °C; CLKOUT disabled.

- 1.  $V_{DD} = 5.0 \text{ V}.$
- 2.  $V_{DD} = 3.3 \text{ V}.$

Figure 39. Typical  $I_{DD}$  with respect to  $f_{SCL}$ 




 $C_{L(itg)}$  = 7 pF; CLKOUT disabled; battery switched on.

- 1.  $V_{DD} = 5 \text{ V}.$
- 2.  $V_{DD} = 3.3 \text{ V}.$


Figure 40. Typical I<sub>DD</sub> as a function of temperature

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus



 $T_{amb}$  = 25 °C;  $f_{CLKOUT}$  = 32 768 Hz.

- 1. 47 pF CLKOUT load.
- 2. 22 pF CLKOUT load.
- 3. 0 pF CLKOUT load.



T<sub>amb</sub> = 25 °C; CLKOUT disabled.

- 1.  $C_{L(itg)} = 12.5 pF$ .
- 2.  $C_{L(itg)} = 7 pF$ .
- 3.  $C_{L(itg)} = 6 pF$ .

Figure 41. Typical  $I_{DD}$  with respect to  $V_{DD}$ 

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus




Table 68. I<sup>2</sup>C-bus characteristics

 $V_{DD}$  = 1.8 V to 5.5 V;  $V_{SS}$  = 0 V;  $T_{amb}$  = -40 °C to +85 °C;  $f_{osc}$  = 32.768 kHz; quartz  $R_s$  = 60 k $\Omega$ ;  $C_L$  = 7 pF; unless otherwise specified. All timing values are valid within the operating supply voltage and temperature range and referenced to  $V_{IL}$  and  $V_{IH}$  with an input voltage swing of  $V_{SS}$  to  $V_{DD}$  [1].

Symbol	Parameter	Conditions		Min	Max	Unit
C <sub>b</sub>	capacitive load for each bus line			-	400	pF
f <sub>SCL</sub>	SCL clock frequency		[2]	0	400	kHz
t <sub>HD;STA</sub>	hold time (repeated) START condition			0.6	-	μs
t <sub>SU;STA</sub>	set-up time for a repeated START condition			0.6	-	μs
$t_{LOW}$	LOW period of the SCL clock			1.3	-	μs
t <sub>HIGH</sub>	HIGH period of the SCL clock			0.6	-	μs
t <sub>r</sub>	rise time of both SDA and SCL signals			20	300	ns
t <sub>f</sub>	fall time of both SDA and SCL signals		[3] [4]	20 × (V <sub>DD</sub> / 5.5 V)	300	ns
t <sub>BUF</sub>	bus free time between a STOP and START condition			1.3	-	μs
t <sub>SU;DAT</sub>	data set-up time			100	-	ns

PCF85263A

All information provided in this document is subject to legal disclaimers.

© NXP B.V. 2021. All rights reserved.


Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 68. I<sup>2</sup>C-bus characteristics...continued

 $V_{DD}$  = 1.8 V to 5.5 V;  $V_{SS}$  = 0 V;  $T_{amb}$  = -40 °C to +85 °C;  $f_{osc}$  = 32.768 kHz; quartz  $R_s$  = 60 k $\Omega$ ;  $C_L$  = 7 pF; unless otherwise specified. All timing values are valid within the operating supply voltage and temperature range and referenced to  $V_{IL}$  and  $V_{IH}$  with an input voltage swing of  $V_{SS}$  to  $V_{DD}$  [1].


Symbol	Parameter	Conditions	Min	N	/lax	Unit
t <sub>HD;DAT</sub>	data hold time		0	-		ns
t <sub>SU;STO</sub>	set-up time for STOP condition		0.6	-		μs
t <sub>VD;DAT</sub>	data valid time		0	0	0.9	μs
t <sub>VD;ACK</sub>	data valid acknowledge time		0	0	.9	μs
t <sub>SP</sub>	pulse width of spikes that must be suppressed by the input filter		0	5	50	ns

- [1]
- A detailed description of the  $l^2$ C-bus specification is given in [8].  $l^2$ C-bus access time between two STARTs or between a START and a STOP condition to this device must be less than one second. [2]
- A device must internally provide a hold time of at least 300 ns for the SDA signal (with respect to the V<sub>IH(min)</sub> of the SCL signal) to bridge the undefined region of the falling edge of SCL.
- The maximum t<sub>f</sub> for the SDA and SCL bus lines is specified at 300 ns. The maximum fall time for the SDA output stage t<sub>f</sub> is specified at 250 ns. This allows series protection resistors to be connected in between the SDA and the SCL pins and the SDA/SCL bus lines without exceeding the maximum specified tf.



Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

# 15 Application information



The data sheet values were obtained using a crystal with an ESR of 60 k $\Omega$ . If a crystal with an ESR of 70 k $\Omega$  is used then the power consumption would increase by a few nA and the start-up time will increase slightly.

# 16 Test information

# 16.1 Quality information


### **UL Component Recognition**



This (component or material) is Recognized by UL. Representative samples of this component have been evaluated by UL and meet applicable UL requirements.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

## 17 Package outline




#### Notes


- 1. Plastic or metal protrusions of 0.15 mm (0.006 inch) maximum per side are not included.
- 2. Plastic or metal protrusions of 0.25 mm (0.01 inch) maximum per side are not included.

OUTLINE		REFER	RENCES	EUROPEAN ISSUE DA		
VERSION	IEC	JEDEC	JEITA		PROJECTION	ISSUE DATE
SOT96-1	076E03	MS-012				<del>99-12-27</del> 03-02-18

Figure 45. Package outline SOT96-1 (SO8), PCF85263AT



Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus



PCF85263A





Figure 48. Package outline SOT552-1 (TSSOP10), PCF85263ATT1



Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

FLIP CHIP DIE-12 I/O 1.185 X 0.935 X 0.22 PKG, 0.25 PITCH S0T2035-1

#### NOTES:

- 1. ALL DIMENSIONS IN MILLIMETERS.
- 2. DIMENSIONING AND TOLERANCING PER ASME Y14.5M-1994.

MAXIMUM SOLDER BALL DIAMETER MEASURED PARALLEL TO DATUM C.

23. PIN A1 FEATURE SHAPE, SIZE AND LOCATION MAY VARY.

DATUM C, THE SEATING PLANE, IS DETERMINED BY THE SPHERICAL CROWNS OF THE SOLDER BALLS.

© NXP B.V. ALL RIGHTS RESERVED

DATE: 24 OCT 2019

= =				
MECHANICAL OUTLINE	STANDARD:	DRAWING NUMBER:	REVISION:	
PRINT VERSION NOT TO SCALE	NON JEDEC	98ASA01491D	0	

Figure 50. Package outline SOT2035-1 (WLCSP12), PCF85263AUK 2 of 2

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

## 18 Handling information

All input and output pins are protected against ElectroStatic Discharge (ESD) under normal handling. When handling Metal-Oxide Semiconductor (MOS) devices ensure that all normal precautions are taken as described in *JESD625-A*, *IEC 61340-5* or equivalent standards.

## 19 Packing information

For tape and reel packing information, please see [4], [5], [6], and [7] in Section 24.

## 20 Soldering of SMD packages

This text provides a very brief insight into a complex technology. A more in-depth account of soldering ICs can be found in Application Note *AN10365 "Surface mount reflow soldering description"*.

#### 20.1 Introduction to soldering

Soldering is one of the most common methods through which packages are attached to Printed Circuit Boards (PCBs), to form electrical circuits. The soldered joint provides both the mechanical and the electrical connection. There is no single soldering method that is ideal for all IC packages. Wave soldering is often preferred when through-hole and Surface Mount Devices (SMDs) are mixed on one printed wiring board; however, it is not suitable for fine pitch SMDs. Reflow soldering is ideal for the small pitches and high densities that come with increased miniaturization.

#### 20.2 Wave and reflow soldering

Wave soldering is a joining technology in which the joints are made by solder coming from a standing wave of liquid solder. The wave soldering process is suitable for the following:

- Through-hole components
- Leaded or leadless SMDs, which are glued to the surface of the printed circuit board

Not all SMDs can be wave soldered. Packages with solder balls, and some leadless packages which have solder lands underneath the body, cannot be wave soldered. Also, leaded SMDs with leads having a pitch smaller than ~0.6 mm cannot be wave soldered, due to an increased probability of bridging.

The reflow soldering process involves applying solder paste to a board, followed by component placement and exposure to a temperature profile. Leaded packages, packages with solder balls, and leadless packages are all reflow solderable.

Key characteristics in both wave and reflow soldering are:

- · Board specifications, including the board finish, solder masks and vias
- Package footprints, including solder thieves and orientation
- · The moisture sensitivity level of the packages
- Package placement
- Inspection and repair
- Lead-free soldering versus SnPb soldering

PCF85263A

All information provided in this document is subject to legal disclaimers.

© NXP B.V. 2021. All rights reserved

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

### 20.3 Wave soldering

Key characteristics in wave soldering are:

- Process issues, such as application of adhesive and flux, clinching of leads, board transport, the solder wave parameters, and the time during which components are exposed to the wave
- Solder bath specifications, including temperature and impurities

### 20.4 Reflow soldering

Key characteristics in reflow soldering are:

- Lead-free versus SnPb soldering; note that a lead-free reflow process usually leads to higher minimum peak temperatures (see <u>Figure 51</u>) than a SnPb process, thus reducing the process window
- Solder paste printing issues including smearing, release, and adjusting the process window for a mix of large and small components on one board
- Reflow temperature profile; this profile includes preheat, reflow (in which the board
  is heated to the peak temperature) and cooling down. It is imperative that the peak
  temperature is high enough for the solder to make reliable solder joints (a solder
  paste characteristic). In addition, the peak temperature must be low enough that the
  packages and/or boards are not damaged. The peak temperature of the package
  depends on package thickness and volume and is classified in accordance with
  Table 69 and Table 70

Table 69. SnPb eutectic process (from J-STD-020D)

Package thickness (mm)	Package reflow temperature (°C)			
	Volume (mm³)			
	< 350	≥ 350		
< 2.5	235	220		
≥ 2.5	220	220		


Table 70. Lead-free process (from J-STD-020D)

Package thickness (mm)	Package reflow temperature (°C)					
	Volume (mm³)					
	< 350	350 to 2000	> 2000			
< 1.6	260	260	260			
1.6 to 2.5	260	250	245			
> 2.5	250	245	245			

Moisture sensitivity precautions, as indicated on the packing, must be respected at all times.


Studies have shown that small packages reach higher temperatures during reflow soldering, see Figure 51.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus




For further information on temperature profiles, refer to Application Note *AN10365* "Surface mount reflow soldering description".


## 21 Footprint information




Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus



PCF85263A





Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

## 22 Appendix

#### 22.1 Real-Time Clock selection

Table 71. Selection of Real-Time Clocks

Type name	Alarm, Timer, Watchdog	Interrupt output	Interface	I <sub>DD</sub> , typical (nA)	Battery backup	Timestamp, tamper input	AEC-Q100 compliant	Special features	Packages
PCF8563	Х	1	I <sup>2</sup> C	250	-	-	-	-	SO8, TSSOP8, HVSON10
PCF8564A	Х	1	I <sup>2</sup> C	250	-	-	-	integrated oscillator caps	WLCSP
PCA8565	Х	1	I <sup>2</sup> C	600	-	-	grade 1	high robustness, T <sub>amb</sub> = -40 °C to 125 °C	TSSOP8, HVSON10
PCA8565A	Х	1	I <sup>2</sup> C	600	-	-	-	integrated oscillator caps, T <sub>amb</sub> = -40 °C to 125 °C	WLCSP
PCF85063	-	1	I <sup>2</sup> C	220	-	-	-	basic functions only, no alarm	HXSON8
PCF85063A	Х	1	I <sup>2</sup> C	220	-	-	-	tiny package	SO8, DFN2626-10
PCF85063B	Х	1	SPI	220	-	-	-	tiny package	DFN2626-10
PCF85263A	Х	2	I <sup>2</sup> C	230	Х	x	-	time stamp, battery backup, stopwatch $\frac{1}{100}$ s	SO8, TSSOP10, TSSOP8, DFN2626-10
PCF85263B	Х	2	SPI	230	Х	х	-	time stamp, battery backup, stopwatch 1/100s	TSSOP10, DFN2626-10
PCF85363A	Х	2	I <sup>2</sup> C	230	Х	X	-	time stamp, battery backup, stopwatch ½ <sub>100</sub> s, 64 Byte RAM	TSSOP10, DFN2626-10
PCF85363B	Х	2	SPI	230	X	Х	-	time stamp, battery backup, stopwatch $^{1}\!\!/_{100}$ s, 64 Byte RAM	TSSOP10, DFN2626-10
PCF8523	х	2	I <sup>2</sup> C	150	Х	-	-	lowest power 150 nA in operation, FM+ 1 MHz	SO8, HVSON8, TSSOP14, WLCSP
PCF2123	Х	1	SPI	100	-	-	-	lowest power 100 nA in operation	TSSOP14, HVQFN16
PCF2127	Х	1	I <sup>2</sup> C and SPI	500	X	Х	-	temperature compensated, quartz built in, calibrated, 512 Byte RAM	SO16
PCF2127A	Х	1	I <sup>2</sup> C and SPI	500	Х	X	-	temperature compensated, quartz built in, calibrated, 512 Byte RAM	SO20
PCF2129	Х	1	I <sup>2</sup> C and SPI	500	Х	Х	-	temperature compensated, quartz built in, calibrated	SO16
PCF2129A	Х	1	I <sup>2</sup> C and SPI	500	х	x	-	temperature compensated, quartz built in, calibrated	SO20
PCA2129	Х	1	I <sup>2</sup> C and SPI	500	Х	x	grade 3	temperature compensated, quartz built in, calibrated	SO16
PCA21125	Х	1	SPI	820	-	-	grade 1	high robustness, T <sub>amb</sub> = -40 °C to 125 °C	TSSOP14

## 23 Abbreviations

Table 72. Abbreviations

Acronym	Description
BCD	Binary Coded Decimal
CMOS	Complementary Metal Oxide Semiconductor
ESD	ElectroStatic Discharge
НВМ	Human Body Model
I <sup>2</sup> C	Inter-Integrated Circuit
IC	Integrated Circuit
LSB	Least Significant Bit

PCF85263A

All information provided in this document is subject to legal disclaimers.

© NXP B.V. 2021. All rights reserved.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Table 72. Abbreviations...continued

Acronym	Description
MSB	Most Significant Bit
MSL	Moisture Sensitivity Level
РСВ	Printed-Circuit Board
POR	Power-On Reset
RTC	Real-Time Clock
SCL	Serial CLock line
SDA	Serial DAta line
SMD	Surface Mount Device

#### 24 References

- [1] JESD22-A114 Electrostatic Discharge (ESD) Sensitivity Testing Human Body Model (HBM)
- [2] JESD22-C101 Field-Induced Charged-Device Model Test Method for Electrostatic-Discharge-Withstand Thresholds of Microelectronic Components
- [3] JESD78 IC Latch-Up Test
- [4] SOT96-1\_118 SO8; Reel pack; SMD, 13", packing information
- [5] SOT505-1\_118 TSSOP8; Reel pack; SMD, 13", packing information
- [6] SOT552-1\_118 TSSOP10; Reel pack; SMD, 13", packing information
- [7] SOT1197-1 115 DFN2626-10; Reel pack; SMD, 7", packing information
- [8] UM10204 I<sup>2</sup>C-bus specification and user manual
- [9] UM10569 Store and transport requirements

## 25 Revision history

Table 73. Revision history

Document ID	Release date	Data sheet status	Change notice	Supersedes
PCF85263A v.5.2	20210922	Product data sheet	202104010DN	PCF85263A v.5.1
	<ul> <li>"Master" or "n language guid</li> <li>"Slave" or "sla guidelines.</li> <li>Section 4.1, Tab</li> </ul>	, revised as follows: naster": revised to "Controller" delines. ave": revised to "Target" or "tar ole 2: revised footnote 1, added ne Packing Method column for	get" to conform with N	XP inclusive language
PCF85263A v.5.1	20210618	Product data sheet	202104008A	PCF85263A v.5
PCF85263A v.5	20210201	Product data sheet	-	PCF85263A v.4.1
PCF85263A v.4.1	20151127	Product data sheet	-	PCF85263A v.4
PCF85263A v.4	20151118	Product data sheet	-	PCF85263A v.3
PCF85263A v.3	20150116	Product data sheet	-	PCF85263A v.2
PCF85263A v.2	20140710	Product data sheet	-	PCF85263A v.1
PCF85263A v.1	20140418	Product data sheet	-	-

PCF85263A

Product data sheet

All information provided in this document is subject to legal disclaimers

© NXP B.V. 2021. All rights reserved.

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

## 26 Legal information

#### 26.1 Data sheet status

Document status <sup>[1][2]</sup>	Product status <sup>[3]</sup>	Definition
Objective [short] data sheet	Development	This document contains data from the objective specification for product development.
Preliminary [short] data sheet	Qualification	This document contains data from the preliminary specification.
Product [short] data sheet	Production	This document contains the product specification.

- [1] Please consult the most recently issued document before initiating or completing a design.
- [2] The term 'short data sheet' is explained in section "Definitions".
- The product status of device(s) described in this document may have changed since this document was published and may differ in case of multiple devices. The latest product status information is available on the Internet at URL <a href="http://www.nxp.com">http://www.nxp.com</a>.

#### 26.2 Definitions

**Draft** — A draft status on a document indicates that the content is still under internal review and subject to formal approval, which may result in modifications or additions. NXP Semiconductors does not give any representations or warranties as to the accuracy or completeness of information included in a draft version of a document and shall have no liability for the consequences of use of such information.

Short data sheet — A short data sheet is an extract from a full data sheet with the same product type number(s) and title. A short data sheet is intended for quick reference only and should not be relied upon to contain detailed and full information. For detailed and full information see the relevant full data sheet, which is available on request via the local NXP Semiconductors sales office. In case of any inconsistency or conflict with the short data sheet, the full data sheet shall prevail.

Product specification — The information and data provided in a Product data sheet shall define the specification of the product as agreed between NXP Semiconductors and its customer, unless NXP Semiconductors and customer have explicitly agreed otherwise in writing. In no event however, shall an agreement be valid in which the NXP Semiconductors product is deemed to offer functions and qualities beyond those described in the Product data sheet.

#### 26.3 Disclaimers

Limited warranty and liability — Information in this document is believed to be accurate and reliable. However, NXP Semiconductors does not give any representations or warranties, expressed or implied, as to the accuracy or completeness of such information and shall have no liability for the consequences of use of such information. NXP Semiconductors takes no responsibility for the content in this document if provided by an information source outside of NXP Semiconductors. In no event shall NXP Semiconductors be liable for any indirect, incidental, punitive, special or consequential damages (including - without limitation - lost profits, lost savings, business interruption, costs related to the removal or replacement of any products or rework charges) whether or not such damages are based on tort (including negligence), warranty, breach of contract or any other legal theory. Notwithstanding any damages that customer might incur for any reason whatsoever, NXP Semiconductors' aggregate and cumulative liability towards customer for the products described herein shall be limited in accordance with the Terms and conditions of commercial sale of NXP Semiconductors

Right to make changes — NXP Semiconductors reserves the right to make changes to information published in this document, including without limitation specifications and product descriptions, at any time and without

notice. This document supersedes and replaces all information supplied prior to the publication hereof.

Suitability for use — NXP Semiconductors products are not designed, authorized or warranted to be suitable for use in life support, life-critical or safety-critical systems or equipment, nor in applications where failure or malfunction of an NXP Semiconductors product can reasonably be expected to result in personal injury, death or severe property or environmental damage. NXP Semiconductors and its suppliers accept no liability for inclusion and/or use of NXP Semiconductors products in such equipment or applications and therefore such inclusion and/or use is at the customer's own risk.

Applications — Applications that are described herein for any of these products are for illustrative purposes only. NXP Semiconductors makes no representation or warranty that such applications will be suitable for the specified use without further testing or modification. Customers are responsible for the design and operation of their applications and products using NXP Semiconductors products, and NXP Semiconductors accepts no liability for any assistance with applications or customer product design. It is customer's sole responsibility to determine whether the NXP Semiconductors product is suitable and fit for the customer's applications and products planned, as well as for the planned application and use of customer's third party customer(s). Customers should provide appropriate design and operating safeguards to minimize the risks associated with their applications and products. NXP Semiconductors does not accept any liability related to any default, damage, costs or problem which is based on any weakness or default in the customer's applications or products, or the application or use by customer's third party customer(s). Customer is responsible for doing all necessary testing for the customer's applications and products using NXP Semiconductors products in order to avoid a default of the applications and the products or of the application or use by customer's third party customer(s). NXP does not accept any liability in this respect

Limiting values — Stress above one or more limiting values (as defined in the Absolute Maximum Ratings System of IEC 60134) will cause permanent damage to the device. Limiting values are stress ratings only and (proper) operation of the device at these or any other conditions above those given in the Recommended operating conditions section (if present) or the Characteristics sections of this document is not warranted. Constant or repeated exposure to limiting values will permanently and irreversibly affect the quality and reliability of the device.

Terms and conditions of commercial sale — NXP Semiconductors products are sold subject to the general terms and conditions of commercial sale, as published at http://www.nxp.com/profile/terms, unless otherwise agreed in a valid written individual agreement. In case an individual agreement is concluded only the terms and conditions of the respective agreement shall apply. NXP Semiconductors hereby expressly objects to applying the customer's general terms and conditions with regard to the purchase of NXP Semiconductors products by customer.

PCF85263A

All information provided in this document is subject to legal disclaimers.

© NXP B.V. 2021. All rights reserved.

## Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

No offer to sell or license — Nothing in this document may be interpreted or construed as an offer to sell products that is open for acceptance or the grant, conveyance or implication of any license under any copyrights, patents or other industrial or intellectual property rights.

**Export control** — This document as well as the item(s) described herein may be subject to export control regulations. Export might require a prior authorization from competent authorities.

Non-automotive qualified products — Unless this data sheet expressly states that this specific NXP Semiconductors product is automotive qualified, the product is not suitable for automotive use. It is neither qualified nor tested in accordance with automotive testing or application requirements. NXP Semiconductors accepts no liability for inclusion and/or use of non-automotive qualified products in automotive equipment or applications. In the event that customer uses the product for design-in and use in automotive applications to automotive specifications and standards, customer (a) shall use the product without NXP Semiconductors' warranty of the product for such automotive applications, use and specifications, and (b) whenever customer uses the product for automotive applications beyond NXP

Semiconductors' specifications such use shall be solely at customer's own risk, and (c) customer fully indemnifies NXP Semiconductors for any liability, damages or failed product claims resulting from customer design and use of the product for automotive applications beyond NXP Semiconductors' standard warranty and NXP Semiconductors' product specifications.

**Translations** — A non-English (translated) version of a document is for reference only. The English version shall prevail in case of any discrepancy between the translated and English versions.

#### 26.4 Trademarks

Notice: All referenced brands, product names, service names and trademarks are the property of their respective owners.

I<sup>2</sup>C-bus — logo is a trademark of NXP B.V.

NXP — wordmark and logo are trademarks of NXP B.V.

PCF85263A **NXP Semiconductors** 

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

### **Tables**

Tab. 3. Price scription   1.5	Tab. 1.	Ordering information	2	Tab. 37.	BSOFF bit - battery switch control (address	
Tab. 3. Pin description         5. Tab. 3. 8         BSRR bit - battery switch control (address set) had been registers         8           Tab. 5. Stop-watch mode time registers         9. Tab. 5. Stop-watch mode time registers         9. Tab. 39. BSM[1:0] bits - battery switch control of address zeb) bit description         42. BSM[1:0] bits - battery switch control of address zeb) bit description         42. BSM[1:0] bits - battery switch control of address zeb) bit description         42. BSM[1:0] bits - battery switch control of address zeb) bit description         42. BSM[1:0] bits - battery switch control of address zeb) bit description         43. BSM[1:0] bits - battery switch control of address zeb) bit description         44. BSM[1:0] bits - battery switch control of address zeb) bit description         45. BSM[1:0] bits - battery switch control of address zeb) bit description         45. BSM[1:0] bits - battery switch control of address zeb) bit description         45. BSM[1:0] bits - battery switch control of address zeb) bit description         45. BSM[1:0] bits - battery switch control of address zeb) bit description         45. BSM[1:0] bits - battery switch control of address zeb) bit description         45. BSM[1:0] bits - battery switch control of address zeb) bit description         45. BSM[1:0] bits - battery switch control of address zeb) bit description         45. BSM[1:0] bits - battery switch control register (address zeb) bit description         45. Battery switch control register (address zeb) bit description         45. Battery switch control register (address zeb) bit description         45. Battery switch control register (address zeb) bit description         45. Battery switch control register (address zeb) bit description	Tab. 2.					41
Tab. 5   Stop-watch mode time registers   9   Tab. 3   Sbowwatch mode time registers   9   Tab. 3   Tab. 3   Sbowwatch mode time registers   9   Tab. 3   Tab. 3   Sbowwatch mode time registers   11   Tab. 4   Tab. 7   Tab. 6   Tab. 7   Tab. 8   Sbowwatch mode (RTCM = 1)   Tab. 8   Sbowwatch mode (RTCM = 1)   Tab. 10   Month assignments in BCD format   Tab. 11   Tab. 10   Month assignments in BCD format   Tab. 11   Tab. 11   Tab. 12   Month assignments in BCD format   Tab. 12   Tab. 12   Alarm1 and alarm2 registers in RTC mode coded in BCD (RTCM = 0)   Tab. 13   Alarm4 and alarm2 registers in RTC mode coded in BCD (RTCM = 0)   Tab. 14   Alarm1 and alarm2 registers in Stop-watch mode coded in BCD (RTCM = 1)   Tab. 14   Alarm4 and alarm2 registers in Stop-watch mode coded in BCD (RTCM = 1)   Tab. 15   Tab. 14   Alarm4 and alarm2 registers in Stop-watch mode coded in BCD (RTCM = 1)   Tab. 14   Alarm4 and alarm2 registers in Stop-watch mode coded in BCD (RTCM = 1)   Tab. 14   Alarm4 and alarm2 registers in Stop-watch mode coded in BCD (RTCM = 1)   Tab. 15   Tab. 15   Tab. 16   Tab. 16   Tab. 16   Tab. 17   Tab. 16   Tab. 17   Tab. 17   Tab. 18   Tab. 18   Tab. 18   Tab. 19   Tab.				Tab. 38.		
Tab. 5   Stop-watch mode time registers overview   10					·	41
Tab. 6.         Control and function registers overview.         10         (address 26h) bit description.         41           Tab. 7.         Time and date registers in RTC mode (RTCM = 0).         11         Tab. 40.         Tab. 41.         BSTH - battery switch control (address 27h) and the compton of the control register (address 27h) bit description.         45           Tab. 10.         Month assignments in BCD format.         13         Tab. 42.         Sh) bit description.         45           Tab. 11.         Time registers in stop-watch mode (RTCM = 1).         15         Tab. 42.         CLFM bit. 1-Pin. IO control register (address 27h) bit description.         46           Tab. 13.         Alarm1 and alarm2 registers in StOP.         16         Tab. 13.         Alarm4 and alarm2 registers in stop-watch mode coded in BCD (RTCM = 1).         10         Tab. 41.         Tab. 42.         Tab. 43.         Tab. 43.         Tab. 43.         Tab. 43.         Tab. 43.         Tab. 44.         Tab. 44.         Tab. 44.         T				Tah 39		
Tab. 7				145. 00.		11
RTCM = 0   11			10	Tab 40	, .	
Tab. 9.         Weekday assignments         11         26h () bit description         45           Tab. 10.         Month assignments in BCD format         13         Tab. 11.         Time registers in stop-watch mode (RTCM         1         Tab. 12.         Alarm 1         Time registers in STC mode coded in BCD (RTCM = 0)         16         Tab. 12.         CLRPM bit - Pin   D control register (address 27h)         46           Tab. 13.         Alarm and alarm2 registers in RTC mode coded in BCD (RTCM = 1)         16         Tab. 43.         TSPULL bit - Pin   D control register (address 27h)         46           Tab. 14.         Alarm and alarm2 registers in stop-watch mode coded in BCD (RTCM = 1)         10         17         Tab. 48.         TSPULL bit - Pin   D control register (address 27h)         46           Tab. 15.         Alarm enables alarm enable control register (address 10h) bit description         20         Tab. 48.         TSPULL bit - Pin   D control register (address 27h)         47           Tab. 15.         Alarm enables alarm enable control register (address 22h) bit description         23         Tab. 41.         TSPM[1:0] bits - Pin   O control register (address 22h) bit description         47         Tab. 45.         TSPM[1:0] bits - Pin   O control register (address 22h) bit description         48         Tab. 47.         TSPM[1:0] bits - Pin   O control register (address 22h) bit description         48         Tab. 49.         Tab. 45	1ab. 1.		44			42
Tab. 9.         Weekday assignments         12         Tab. 10.         Incoming assignments in BCD format         13         13         Tab. 11.         Time registers in stop-watch mode (RTCM = 1).         13         13         13         (address 27h) bit description         46           Tab. 12.         Alarm1 and alarm2 registers in RTC mode coded in BCD (RTCM = 0).         16         Tab. 13.         Alarm2 enables - alarm enables control register (address 10h) bit description.         17         Tab. 43.         Tab. 41.         Alarm1 and alarm2 registers in stop-watch mode coded in BCD (RTCM = 1).         10         Tab. 45.         TSb. LIL bit - Pin   O control register (address 27h) bit description.         47           Tab. 14.         Alarm1 and alarm2 registers in stop-watch mode coded in BCD (RTCM = 1).         10         Tab. 47.         TSb. LIL bit - Pin   O control register (address 27h) bit description.         47         TSb. LIL bit - Pin   O control register (address 27h) bit description.         47         TSb. LIL bit - Pin   O control register (address 27h) bit description.         47         TSb. LIL bit - Pin   O control register (address 27h) bit description.         48         TSb. LIL bit - Pin   O control register (address 27h) bit description.         48         TSb. LIL bit - Pin   O control register (address 27h) bit description.         48         TSb. LIL bit - Pin   O control register (address 27h) bit description.         48         TSb. LIL bit - Pin   O control register (address 27h) bit description. <td< td=""><td>T-b 0</td><td></td><td></td><td>1ab. 41.</td><td></td><td>45</td></td<>	T-b 0			1ab. 41.		45
Tab. 10.         Month assignments in BCD format         13         (address 27h) bit description         46           Tab. 11.         Time registers in stop-watch mode (RTCM = 1)         15         Tab. 43.         CLKPM bit - Pin. I O control register (address 27h)         46           Tab. 12.         Alarm1 and alarm2 registers in RTC mode coded in BCD (RTCM = 0)         16         Tab. 43.         Tab. 14.         Tab. 15.         Alarm enables - alarm enable control register (address 10h) bit description         17         Tab. 44.         Tab. 14.         Alarm1 and alarm2 registers in stop-watch mode coded in BCD (RTCM = 1)         20         Tab. 44.         Tab. 14.         Alarm1 and alarm2 registers in stop-watch mode coded in BCD (RTCM = 1)         20         Tab. 45.         TSL bit. Pin. IO control register (address 27h)         47           Tab. 15.         Alarm2 enables- alarm enable control register (address 20h) bit description         20         Tab. 48.         TSPM[1:0] bits - Pin. IO control register (address 22h) bit description         47           Tab. 16.         WatchDog vatchloog control and register (address 22h) and table register (address 22h) and table register (address 22h) and table register (address 22h)         23         Tab. 47.         TSIM bit - Pin. IO control register (address 22h) and table register (address 22h) and table register (address 22h)         Tab. 48.         INTA battery molt on control register (address 22h) and table register (address 22h) and table register (address 22h) and table register (				T   40		45
Tab. 12				Tab. 42.		
Tab. 12			13			46
Tab. 12.         Alarm1 and alarm2 registers in RTC mode coded in BCD (RTCM = 0)         16           Tab. 13.         Alarm2 enables- alarm enable control register (address 20h) bit description         17           Tab. 14.         Alarm1 and alarm2 registers in stop-watch mode coded in BCD (RTCM = 1)         20           Tab. 15.         Alarm enables- alarm enable control register (address 20h) bit description         20           Tab. 16.         WatchDog - WatchDog control and register (address 2Dh) bit description         23           Tab. 17.         WatchDog - WatchDog control and register (address 2Dh) bit description         23           Tab. 18.         RAM byte - 8-bit RAM register (address 2Dh) bit description         23           Tab. 19.         Tab. 40.         ITRAPM[1:0] bits - Pin_IO control register (address 2Ph) in description         48           Tab. 20.         Tab. 40.         WatchDog - WatchDog control and register (address 2Ph) in description         23           Tab. 19.         Tab. 40.         ITRAPM[1:0] bits - Pin_IO control register (address 2Ph) in description         48           Tab. 21.         Timestamp register (address 2Ph) in description         26         Tab. 40.         ITRAPM[1:0] bits - Pin_IO control register (address 2Ph) in description         49           Tab. 22.         Timestamp registers in RTC mode (RTCM (RTCM = 1)         27         Tab. 40.         Tab. 40.	Tab. 11.			Tab. 43.		
Coded in BCD (RTCM = 0)			15			46
Tab. 13.         Alarm_ enables- alarm enable control register (address 10h) bit description         17         Tab. 14.         Alarm and alarm2 registers in stop-watch mode coded in BCD (RTCM = 1)         20         Tab. 46.         TsPM(1:0) bits - Pin_IO control register (address 27h)         47           Tab. 15.         Alarm_ enables- alarm enable control register (address 21h) bit description         20         Tab. 48.         TsPM(1:0) bits - Pin_IO control register (address 27h)         47           Tab. 16.         WatchDog - WatchDog control and register (address 27h) bit description         23         Tab. 48.         INTAPM[1:0] bits - Pin_IO control register (address 27h) bit description         48           Tab. 17.         WatchDog durations         23         Tab. 50.         Intab. 50.	Tab. 12.	Alarm1 and alarm2 registers in RTC mode		Tab. 44.		
register (address 10h) bit description   17		coded in BCD (RTCM = 0)	16		(address 27h)	46
Tab. 14.         Alarm1 and alarm2 registers in stop-watch mode coded in BCD (RTCM = 1)         Tab. 15.         Tab. 16.         TSPM[1:0] bits - Pin_IO control register (address 27h)         48           Tab. 16.         WatchDog ow AutchDog control and register (address 2Dh) bit description         23         Tab. 47.         TSIM bit - Pin_IO control register (address 27h)         48           Tab. 17.         WatchDog durations         23         Tab. 48.         INTAPM[1:0] bits - Pin_IO control register (address 27h) bit description         49           Tab. 18.         ARM byte - 8-bit RAM register (address 22h) bit description         25         Tab. 49.         INTA battery mode         49           Tab. 19.         TSR_mode - timestamp mode control register (address 22h) bit description         26         Tab. 50.         Function - chip function control register (address 28h) bit description         50           Tab. 20.         Timestamp registers in stop-watch mode (RTCM = 0)         28         Tab. 51.         100TH bit - Function control register (address 28h) bit description         50           Tab. 21.         Timestamp registers in stop-watch mode (RTCM = 0)         29         Tab. 55.         FTCM bit - Function control register (address 28h) bit description         51         Tab. 55.         STOPM bit - Function control register (address 28h) bit description         51         Tab. 54.         Tab. 57.         COFEM bit - Function control register (ad	Tab. 13.	Alarm_enables- alarm enable control		Tab. 45.	TSL bit - Pin_IO control register (address	
mode coded in BCD (RTCM = 1)		register (address 10h) bit description	17		27h)	47
mode coded in BCD (RTCM = 1)	Tab. 14.	Alarm1 and alarm2 registers in stop-watch		Tab. 46.	TSPM[1:0] bits - Pin IO control register	
Tab. 15.         Alarm_enables- alarm enable control register (address 10h) bit description         20         27h)         27h)         48         47.         TSIM bit - Pin_IO control register (address 2h)         48         48         27h)         48         48         48         18			20		(address 27h)	47
Tab. 16.   WatchDog - WatchDog control and register (address 2Dh) bit description 23   Tab. 48.   INTAPM[1:0] bits - Pin_IO control register (address 2Dh) bit description 23   Tab. 49.   INTA battery mode 49   Tab. 50.   Function - chip function control register (address 2Bh) bit description 25   Tab. 51.   Tab. 49.   INTA battery mode 49   Tab. 50.   Function - chip function control register (address 2Bh) bit description 26   Tab. 51.   Tab.	Tab. 15.	· · · · · · · · · · · · · · · · · · ·		Tab. 47.		
Tab. 16.         WatchDog - WatchDog control and register (address 2Dh) bit description         23         Tab. 17.         WatchDog durations         23         Tab. 18.         RAM_ byte - 8-bit RAM register (address 2Ch) bit description         25         Tab. 18.         RAM_ byte - 8-bit RAM register (address 2Ch) bit description         25         Tab. 50.         Function - chip function control register (address 28h) bit description control register (address 23h) bit description         50         Tab. 50.         Function - chip function control register (address 28h) bit description control register (address 28h) bit description         50         Tab. 51.         Tab. 51.         Tab. 51.         Tab. 51.         Tab. 52.         Pi[1:0] bits - Function control register (address 28h) bit description         50           Tab. 20.         Tab. 51.         Tab. 52.         Pi[1:0] bits - Function control register (address 28h)         50           Tab. 21.         Timestamp registers in stop-watch mode (RTCM = 1)         29         Tab. 53.         RTCM bit - Function control register (address 28h)         50           Tab. 22.         Offset offset register (address 24h) bit description         30         Tab. 53.         RTCM bit - Function control register (address 28h)         51           Tab. 24.         Offset values         31         Tab. 55.         STOPM bit - Function control register (address 28h)         51           Tab. 25.         Correction pulses			20			48
(address 2Dh) bit description         23         Tab. 47. WatchDog durations         49           Tab. 18. RAM_byte -8-bit RAM register (address 2Ch) bit description         25         Tab. 50. Function - chip function control register (address 28h) bit description         50           Tab. 19. TSR_mode - timestamp mode control register (address 23h) bit description         26         Tab. 51. 100TH bit - Function control register (address 28h) bit description megisters in RTC mode (RTCM = 0)         7ab. 51. 100TH bit - Function control register (address 28h) megister (address 28h)         50           Tab. 20. Timestamp registers in stop-watch mode (RTCM = 1)         29         Tab. 52. P[1:0] bits - Function control register (address 28h)         50           Tab. 21. Timestamp register (address 24h) bit description         30         Tab. 53. RTCM bit - Function control register (address 28h)         50           Tab. 22. Offset - offset register (address 24h) bit description         30         Tab. 54. RTC time counting modes         51           Tab. 23. OFFM bit - oscillator control register (address 25h)         31         Tab. 55. STOPM bit - Function control register (address 28h)         51           Tab. 24. Offset values         31         Tab. 56. Orrection pulses for OFFM = 0         32         Tab. 57. COF[2:0] bits - Function control register (address 28h)         52           Tab. 27. INTA and INTB interrupt control bits         35         Tab. 59. Flags - Flag status register (address 28h)         53<	Tab. 16.			Tab. 48.		
Tab. 17.         WatchDog durations         .23         Tab. 50.         Incition - chip function control register (address 28h) bit description         .50         Function - chip function control register (address 28h) bit description         .50         Tab. 50.         Function - chip function control register (address 28h) bit description         .50         Tab. 50.         Function - chip function control register (address 28h) bit description         .50         Tab. 50.         Function - chip function control register (address 28h) bit description         .50         Tab. 51.         Tab. 51.         Tab. 51.         Tab. 52.         Tab. 52.         Tab. 52.         Tab. 53.         Tab. 54.         Tab. 55.         Tab. 55.         Tab. 55.         Tab. 56.         Tab. 57.         Tab. 57. <td></td> <td></td> <td> 23</td> <td></td> <td></td> <td> 49</td>			23			49
Tab. 18.         RAM_ byte - 8-bit RAM register (address 2h) bit description         25           Tab. 19.         TSR_mode - timestamp mode control register (address 23h) bit description         26           Tab. 20.         Timestamp registers in RTC mode (RTCM = 0)         28           Tab. 21.         Timestamp registers in stop-watch mode (RTCM = 1)         29           Tab. 22.         Offset - offset register (address 24h) bit description         30           Tab. 23.         OFFM bit - oscillator control register (address 24h)         30           Tab. 24.         Offset values         31           Tab. 25.         Correction pulses for OFFM = 0         32           Tab. 26.         Correction pulses for OFFM = 1         32           Tab. 27.         INTA and INTB interrupt control bits         35           Tab. 29.         Oscillator - oscillator control register (address 25h)         35           Tab. 30.         CLKIV bit - oscillator control register (address 25h)         35           Tab. 31.         Tab. 32.         Tab. 33         Tab. 34.         Tab. 35.         Tab. 34.         Tab. 34.         Tab. 35.	Tab 17			Tab 49		
2Ch   bit description   .25			20			0
Tab. 19.         TSR_mode - timestamp mode control register (address 23h) bit description         26         Tab. 51.         100TH bit - Function control register (address 28h)         50           Tab. 20.         Timestamp registers in RTC mode (RTCM e 0)         28         Tab. 52.         PI[1/10] bits - Function control register (address 28h)         50           Tab. 21.         Timestamp registers in stop-watch mode (RTCM e 1)         29         Tab. 53.         RTCM bit - Function control register (address 28h)         51           Tab. 22.         Offset - offset register (address 24h) bit description         30         Tab. 54.         RTC time counting modes         51           Tab. 23.         OFFM bit - oscillator control register (address 25h)         31         Tab. 56.         Oscillator stop control when STOPM = 1         51           Tab. 24.         Offset values         31         Tab. 57.         COF[2:0] bits - Function control register (address 28h)         51           Tab. 25.         Correction pulses for OFFM = 0         32         32         Tab. 56.         Oscillator stop control when STOPM = 1         51           Tab. 26.         Correction pulses for OFFM = 1         32         Tab. 58.         Clock duty cycles         52           Tab. 27.         INTA and INTB interrupt control bits         35         Tab. 59.         Flags - Flag status register (ad	100.		25	145. 00.	•	50
Tab. 20.   Timestamp registers in RTC mode (RTCM	Tah 10		20	Tah 51		00
Tab. 20.         Timestamp registers in RTC mode (RTCM = 0)         28         Tab. 52.         PI[1:0] bits - Function control register (address 28h)         50           Tab. 21.         Timestamp registers in stop-watch mode (RTCM = 1)         29         Tab. 53.         RTCM bit - Function control register (address 28h)         51           Tab. 22.         Offset register (address 24h) bit description         30         Tab. 54.         RTC time counting modes         51           Tab. 23.         OFFM bit - oscillator control register (address 25h)         31         Tab. 55.         STOPM bit - Function control register (address 28h)         51           Tab. 24.         Offset values         31         Tab. 56.         Oscillator stop control when STOPM = 1         51           Tab. 25.         Correction pulses for OFFM = 0         32         Tab. 57.         COF[2:0] bits - Function control register (address 28h)         52           Tab. 26.         Correction pulses for OFFM = 1         32         Tab. 57.         COF[2:0] bits - Function control register (address 28h)         52           Tab. 27.         INTA and INTB interrupt control bits         35         Tab. 58.         Clock duty cycles         52           Tab. 28.         Definition of interrupt control bits         35         Tab. 59.         Flags - Flag status register (address 28h)         53	100. 10.		26	145. 51.		50
Tab. 21.   Timestamp registers in stop-watch mode (RTCM = 1)   29	Tah 20		20	Tah 52		00
Tab. 21.         Timestamp registers in stop-watch mode (RTCM = 1)         29         Tab. 53.         RTCM bit - Function control register (address 28h)         51           Tab. 22.         Offset - offset register (address 24h) bit description         30         Tab. 54.         RTC time counting modes         51           Tab. 23.         OFFM bit - oscillator control register (address 25h)         31         Tab. 55.         STOPM bit - Function control register (address 28h)         51           Tab. 24.         Offset values         31         Tab. 56.         Oscillator stop control when STOPM = 1         51           Tab. 25.         Correction pulses for OFFM = 0         32         (address 28h)         52           Tab. 26.         Correction pulses for OFFM = 1         32         Tab. 56.         Oscillator stop control when STOPM = 1         51           Tab. 27.         INTA and INTB interrupt control bits         35         Tab. 57.         Clock duty cycles         52           Tab. 28.         Definition of interrupt control bits         35         Tab. 59.         Flags - Flag status register (address 2Bh) bit description         53           Tab. 30.         CLKIV bit - oscillator control register (address 25h) bit description         38         Tab. 60.         Reset - software reset control (address 25h)         55           Tab. 31. <td< td=""><td>1ab. 20.</td><td></td><td>28</td><td>1ab. 52.</td><td></td><td>50</td></td<>	1ab. 20.		28	1ab. 52.		50
(RTCM = 1)       29       (address 28h)       51         Tab. 22. Offset - offset register (address 24h) bit description       30       Tab. 54. RTC time counting modes       51         Tab. 23. OFFM bit - oscillator control register (address 25h)       31       Tab. 55. STOPM bit - Function control register (address 28h)       51         Tab. 24. Offset values       31       Tab. 56. Oscillator stop control when STOPM = 1       51         Tab. 25. Correction pulses for OFFM = 0       32       (address 28h)       52         Tab. 26. Correction pulses for OFFM = 1       32       Tab. 58. Clock duty cycles       52         Tab. 27. INTA and INTB interrupt control bits       35       Tab. 59. Flags status register (address 28h)       52         Tab. 28. Definition of interrupt control register (address 25h) bit description       38       Tab. 59. Flag status register (address 28h)       53         Tab. 30. CLKIV bit - oscillator control register (address 25h) bit description       38       Tab. 60. Reset - software reset control (address 25h) bit description       54         Tab. 31. 12_24 bit - oscillator control register (address 25h)       38       Tab. 61. Registers reset values       55         Tab. 32. LOWJ bit - oscillator control register (address 25h)       38       Tab. 63. Counter stop signal       57         Tab. 34. CL[1:0] bits - oscillator control register (address 25h)       54	Tab 21		20	Tab 52		50
Tab. 22. Offset - offset register (address 24h) bit description	1ab. Z 1.		20	1ab. 55.		<b>E</b> 1
description	Tab 22		29	Tob E1		
Tab. 23.         OFFM bit - oscillator control register (address 25h)         (address 25h)         51           Tab. 24.         Offset values         31         Tab. 56.         Oscillator stop control when STOPM = 1         51           Tab. 25.         Correction pulses for OFFM = 0         32         (address 28h)         52           Tab. 26.         Correction pulses for OFFM = 1         32         Tab. 58.         Clock duty cycles         52           Tab. 27.         INTA and INTB interrupt control bits         35         Tab. 59.         Flags - Flag status register (address 28h)         52           Tab. 28.         Definition of interrupt control bits         35         Tab. 59.         Flags - Flag status register (address 28h)         53           Tab. 29.         Oscillator - oscillator control register (address 25h) bit description         38         Tab. 60.         Reset - software reset control (address 2Fh) bit description         54           Tab. 30.         CLKIV bit - oscillator control register (address 25h)         38         Tab. 61.         Registers reset values         55           Tab. 31.         12 24 bit - oscillator control register (address 25h)         38         Tab. 62.         Stop_enable - control of STOP bit (address 2Fh)         56           Tab. 32.         LOWJ bit - oscillator control register (address 25h)         39	1ab. 22.		20			51
(address 25h)       31       Tab. 56.       Oscillator stop control when STOPM = 1       51         Tab. 24.       Offset values       31       Tab. 57.       COF[2:0] bits - Function control register         Tab. 25.       Correction pulses for OFFM = 0       32       (address 28h)       52         Tab. 26.       Correction pulses for OFFM = 1       32       Tab. 58.       Clock duty cycles       52         Tab. 27.       INTA and INTB interrupt control bits       35       Tab. 59.       Flags - Flag status register (address 2Bh)       53         Tab. 28.       Definition of interrupt control bits       35       Tab. 59.       Flags - Flag status register (address 2Bh)       53         Tab. 29.       Oscillator - oscillator control register (address 25h) bit description       38       Tab. 60.       Reset - software reset control (address 25h) bit description       54         Tab. 30.       CLKIV bit - oscillator control register (address 25h)       38       Tab. 61.       Registers reset values       55         Tab. 31.       12_24 bit - oscillator control register (address 25h)       38       Tab. 62.       Stop_enable - control of STOP bit (address 25h)       56         Tab. 32.       LOWJ bit - oscillator control register (address 25h)       39       Tab. 64.       12C target address byte       61	T-1- 00		30	1ab. 55.		-4
Tab. 24.         Offset values         31         Tab. 57.         COF[2:0] bits - Function control register (address 28h)         52           Tab. 25.         Correction pulses for OFFM = 1         32         Tab. 58.         Clock duty cycles         52           Tab. 26.         Correction pulses for OFFM = 1         32         Tab. 58.         Clock duty cycles         52           Tab. 27.         INTA and INTB interrupt control bits         35         Tab. 59.         Flags - Flag status register (address 28h)         53           Tab. 28.         Definition of interrupt control bits         35         Tab. 59.         Flags - Flag status register (address 28h)         53           Tab. 29.         Oscillator control register (address 25h) bit description         38         Tab. 60.         Reset - software reset control (address 25h) bit description         54           Tab. 30.         CLKIV bit - oscillator control register (address 25h)         38         Tab. 61.         Registers reset values         55           Tab. 31.         12_24 bit - oscillator control register (address 25h)         38         Tab. 62.         Stop_enable - control of STOP bit (address 25h)         56           Tab. 32.         LOWJ bit - oscillator control register (address 25h)         39         Tab. 63.         Counter stop signal         57           Tab. 33.	1ab. 23.		0.4	T   50		
Tab. 25. Correction pulses for OFFM = 0	T 1 04	· ·			·	51
Tab. 26. Correction pulses for OFFM = 1				lab. 57.		
Tab. 27. INTA and INTB interrupt control bits						
Tab. 28. Definition of interrupt control bits						52
Tab. 29. Oscillator - oscillator control register (address 25h) bit description				Tab. 59.		
(address 25h) bit description382Fh) bit description54Tab. 30. CLKIV bit - oscillator control register (address 25h)38Tab. 61. Registers reset values55Tab. 31. 12_24 bit - oscillator control register (address 25h)38Tab. 62. Stop_enable - control of STOP bit (address 2Eh)56Tab. 32. LOWJ bit - oscillator control register (address 25h)38Tab. 63. Counter stop signal57Tab. 32. LOWJ bit - oscillator control register (address 25h)39Tab. 64. I2C target address byte61Tab. 33. OSCD[1:0] bits - oscillator control register (address 25h)39Tab. 66. Limiting values65Tab. 34. CL[1:0] bits - oscillator control register (address 25h)39Tab. 67. Characteristics65Tab. 35. IO pin behavior in battery mode40Tab. 69. SnPb eutectic process (from J-STD-020D)80Tab. 36. Battery_switch - battery switch controlTab. 71. Selection of Real-Time Clocks85			35		bit description	53
Tab. 30. CLKIV bit - oscillator control register (address 25h)	Tab. 29.	Oscillator - oscillator control register		Tab. 60.		
(address 25h)38Tab. 62.Stop_enable - control of STOP bit (addressTab. 31.12_24 bit - oscillator control register (address 25h)2Eh)56Tab. 32.LOWJ bit - oscillator control register (address 25h)7ab. 64.12C target address byte61Tab. 33.OSCD[1:0] bits - oscillator control register (address 25h)7ab. 65.Application configuration62Tab. 34.CL[1:0] bits - oscillator control register (address 25h)7ab. 67.Characteristics65Tab. 34.CL[1:0] bits - oscillator control register (address 25h)7ab. 68.12C-bus characteristics70Tab. 35.IO pin behavior in battery mode407ab. 69.SnPb eutectic process (from J-STD-020D)80Tab. 36.Battery_switch - battery switch control7ab. 71.Selection of Real-Time Clocks85		(address 25h) bit description	38		2Fh) bit description	. 54
Tab. 31.12_24 bit - oscillator control register (address 25h)38Tab. 63.Counter stop signal57Tab. 32.LOWJ bit - oscillator control register (address 25h)39Tab. 64.I2C target address byte61Tab. 33.OSCD[1:0] bits - oscillator control register (address 25h)39Tab. 65.Application configuration62Tab. 34.CL[1:0] bits - oscillator control register (address 25h)39Tab. 67.Characteristics65Tab. 34.CL[1:0] bits - oscillator control register (address 25h)Tab. 68.I2C-bus characteristics70Tab. 35.IO pin behavior in battery mode40Tab. 70.Lead-free process (from J-STD-020D)80Tab. 36.Battery_switch - battery switch controlTab. 71.Selection of Real-Time Clocks85	Tab. 30.	CLKIV bit - oscillator control register		Tab. 61.	Registers reset values	55
(address 25h)38Tab. 63.Counter stop signal57Tab. 32.LOWJ bit - oscillator control register (address 25h)39Tab. 64.I2C target address byte61Tab. 33.OSCD[1:0] bits - oscillator control register (address 25h)Tab. 66.Limiting values65Tab. 34.CL[1:0] bits - oscillator control register (address 25h)Tab. 67.Characteristics65Tab. 68.I2C-bus characteristics70(address 25h)39Tab. 69.SnPb eutectic process (from J-STD-020D)80Tab. 35.IO pin behavior in battery mode40Tab. 70.Lead-free process (from J-STD-020D)80Tab. 36.Battery_switch - battery switch controlTab. 71.Selection of Real-Time Clocks85		(address 25h)	38	Tab. 62.	Stop_enable - control of STOP bit (address	
Tab. 32.LOWJ bit - oscillator control register (address 25h)Tab. 64.I2C target address byte61Tab. 33.OSCD[1:0] bits - oscillator control register (address 25h)Tab. 66.Limiting values65Tab. 34.CL[1:0] bits - oscillator control register (address 25h)Tab. 67.Characteristics65Tab. 68.I2C-bus characteristics70(address 25h)39Tab. 69.SnPb eutectic process (from J-STD-020D)80Tab. 35.IO pin behavior in battery mode40Tab. 70.Lead-free process (from J-STD-020D)80Tab. 36.Battery_switch - battery switch controlTab. 71.Selection of Real-Time Clocks85	Tab. 31.	12_24 bit - oscillator control register			2Eh)	56
Tab. 32.LOWJ bit - oscillator control register (address 25h)Tab. 64.I2C target address byte61Tab. 33.OSCD[1:0] bits - oscillator control register (address 25h)Tab. 66.Limiting values65Tab. 34.CL[1:0] bits - oscillator control register (address 25h)Tab. 67.Characteristics65Tab. 68.I2C-bus characteristics70(address 25h)39Tab. 69.SnPb eutectic process (from J-STD-020D)80Tab. 35.IO pin behavior in battery mode40Tab. 70.Lead-free process (from J-STD-020D)80Tab. 36.Battery_switch - battery switch controlTab. 71.Selection of Real-Time Clocks85		(address 25h)	38	Tab. 63.	Counter stop signal	57
(address 25h)       39       Tab. 65.       Application configuration       62         Tab. 33.       OSCD[1:0] bits - oscillator control register (address 25h)       39       Tab. 66.       Limiting values       65         Tab. 34.       CL[1:0] bits - oscillator control register (address 25h)       Tab. 68.       I2C-bus characteristics       70         Tab. 35.       IO pin behavior in battery mode       40       Tab. 70.       Lead-free process (from J-STD-020D)       80         Tab. 36.       Battery_switch - battery switch control       Tab. 71.       Selection of Real-Time Clocks       85	Tab. 32.			Tab. 64.		
Tab. 33.OSCD[1:0] bits - oscillator control register (address 25h)Tab. 66.Limiting values65Tab. 34.CL[1:0] bits - oscillator control register (address 25h)Tab. 68.I2C-bus characteristics70Tab. 35.IO pin behavior in battery mode40Tab. 69.SnPb eutectic process (from J-STD-020D)80Tab. 36.Battery_switch - battery switch controlTab. 71.Selection of Real-Time Clocks85			39	Tab. 65.		
(address 25h)39Tab. 67. Characteristics65Tab. 34. CL[1:0] bits - oscillator control registerTab. 68. I2C-bus characteristics70(address 25h)39Tab. 69. SnPb eutectic process (from J-STD-020D)80Tab. 35. IO pin behavior in battery mode40Tab. 70. Lead-free process (from J-STD-020D)80Tab. 36. Battery_switch - battery switch controlTab. 71. Selection of Real-Time Clocks85	Tab. 33.					
Tab. 34. CL[1:0] bits - oscillator control register (address 25h)	50.		39			
(address 25h)	Tab 34					
Tab. 35. IO pin behavior in battery mode			30			
Tab. 36. Battery_switch - battery switch control Tab. 71. Selection of Real-Time Clocks85	Tah 35					
<i>'</i> = '			+0			
(addices 2011) bit description	iau. 30.		40			
		(addices zon) bit description	+0	1ab. 12.	/ NON-CYTALIONS	03

PCF85263A

Product data sheet

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

Tab. 73. Revision history ......86

## **Figures**

Fig. 1.	Block diagram of PCF85263A	3	Fig. 33.	STOP release timing	57
Fig. 2.	Pin configuration for PCF85263AT (SO8)		Fig. 34.	I2C read and write protocol	
Fig. 3.	Pin configuration for PCF85263ATL		Fig. 35.	I2C read and write signaling	
Ū	(DFN2626-10)	4	Fig. 36.	Application example	
Fig. 4.	Pin configuration for PCF85263ATT		Fig. 37.	Application example timing	
Ü	(TSSOP8)	4	Fig. 38.	Device diode protection diagram of	
Fig. 5.	Pin configuration for PCF85263ATT1		J	PCF85263A	64
Ü	(TSSOP10)	5	Fig. 39.	Typical IDD with respect to fSCL	
Fig. 6.	Pin configuration for PCF85263AUK		Fig. 40.	Typical IDD as a function of temperature	
Ü	(WLCSP12)	5	Fig. 41.	Typical IDD with respect to VDD	
Fig. 7.	Address register incrementing		Fig. 42.	Oscillator frequency variation with respect	
Fig. 8.	Register map		3	to VDD	70
Fig. 9.	Time mode register set selection		Fig. 43.	I2C-bus timing diagram; rise and fall times	
Fig. 10.	OS status bit		3	refer to 30 % and 70 %	7′
Fig. 11.	Data flow for the time function		Fig. 44.	Application diagram for PCF85263A	
Fig. 12.	Data flow for the stop-watch function		Fig. 45.	Package outline SOT96-1 (SO8),	
Fig. 13.	Alarm1 and alarm2 function block diagram		J	PCF85263AT	73
Ü	(RTC mode)		Fig. 46.	Package outline SOT1197-1	
Fig. 14.	Alarm1 and alarm2 function block diagram		3	(DFN2626-10), PCF85263ATL	74
Ü	(stop-watch mode)		Fig. 47.	Package outline SOT505-1 (TSSOP8),	
Fig. 15.	WatchDog repeat mode		J	PCF85263ATT	75
Fig. 16.	WatchDog single shot mode		Fig. 48.	Package outline SOT552-1 (TSSOP10),	
Fig. 17.	Timestamp		J	PCF85263ATT1	76
Fig. 18.	Example battery switch-over timestamp		Fig. 49.	Package outline SOT2035-1 (WLCSP12),	
Fig. 19.	Example TS pin driven timestamp		Ü	PCF85263AUK 1 of 2	77
Fig. 20.	Offset calibration calculation workflow		Fig. 50.	Package outline SOT2035-1 (WLCSP12),	
Fig. 21.	Result of offset calibration		Ü	PCF85263AUK 2 of 2	78
Fig. 22.	Interrupt pulse width		Fig. 51.	Temperature profiles for large and small	
Fig. 23.	Interrupt selection		Ü	components	8
Fig. 24.	Threshold voltage switching hysteresis		Fig. 52.	Footprint information for reflow soldering of	
Fig. 25.	Switching at Vth		· ·	SOT96-1 (SO8), PCF85263AT	8
Fig. 26.	Switching at VBAT		Fig. 53.	Footprint information for reflow soldering of	
Fig. 27.	Switching at the higher of VBAT or Vth		· ·	SOT1197-1 (DFN2626-10),PCF85263ATL	82
Fig. 28.	Switching at the lower of VBAT or Vth		Fig. 54.	Footprint information for reflow soldering of	
Fig. 29.	TS pin	47	_	SOT505-1 (TSSOP8),PCF85263ATT	83
Fig. 30.	INTA pin		Fig. 55.	Footprint information for reflow soldering of	
Fig. 31.	Software reset command		-	SOT552-1 (TSSOP10), PCF85263ATT1	84
Fig. 32.	CPR and STOP bit functional diagram	57			

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

### **Contents**

1	General description	1	7.10	Oscillator register	38
2	Features and benefits	1	7.10.1	CLKIV: invert the clock output	38
3	Applications	1	7.10.2	OFFM: offset calibration mode	38
4	Ordering information	2	7.10.3	12_24: 12 hour or 24 hour clock	38
4.1	Ordering options		7.10.4	LOWJ: low jitter mode	
5	Block diagram		7.10.5	OSCD[1:0]: quartz oscillator drive control	
6	Pinning information		7.10.6	CL[1:0]: quartz oscillator load capacitance	
6.1	Pinning		7.11	Battery switch register	
6.2	Pin description		7.11.1	BSOFF: battery switch on/off control	
7	Functional description		7.11.2	BSRR: battery switch internal refresh rate	
7.1	Registers organization overview		7.11.3	BSM[1:0]: battery switch mode	
7.1.1	Time mode registers		7.11.3.1		
7.1.1.1	RTC mode time registers overview (RTCM		7.11.3.2		
7.1.1.1	= 0)	Ω	7.11.3.2		40
7.1.1.2	Stop-watch mode time registers (RTCM =	0	7.11.5.5	level, BSM[1:0] = 10	11
1.1.1.2	1)	0	7.11.3.4		44
7.1.2			7.11.3.4		11
	Control registers overview		7 11 1	level, BSM[1:0] = 11	
7.2 7.2.1	RTC mode time and date registers  Definition of BCD		7.11.4	BSTH: threshold voltage control  Battery switch interrupts	
			7.11.5	•	
7.2.2	OS: Oscillator stop		7.12	Pin_IO register	
7.2.3	EMON: event monitor		7.12.1	CLKPM: CLK pin mode control	
7.2.4	Definition of weekdays		7.12.2	TSPULL: TS pin pull-up resistor value	
7.2.5	Definition of months		7.12.3	TSL: TS pin level sense	
7.2.6	Setting and reading the time in RTC mode		7.12.4	TSPM[1:0]: TS pin I/O control	
7.3	Stop-watch mode time registers	14	7.12.4.1	1 1	
7.3.1	Setting and reading the time in stop-watch		7.12.4.2		
	mode		7.12.4.3	•	
7.4	Alarms		7.12.5	TSIM: TS pin input type control	
7.4.1	Alarms in RTC mode		7.12.5.1		
7.4.1.1	Alarm1 and alarm2 registers in RTC mode		7.12.6	INTAPM[1:0]: INTA pin mode control	
7.4.1.2	Alarm1 and alarm2 control in RTC mode	17	7.12.6.1	L 3	
7.4.1.3	Alarm1 and alarm2 function in RTC mode	18	7.12.6.2	! INTAPM[1:0]: clock data	49
7.4.2	Alarms in stop-watch mode	19	7.12.6.3	INTAPM[1:0]: battery mode indication	49
7.4.2.1	Alarm1 and alarm2 registers in stop-watch		7.13	Function register	50
	mode	19	7.13.1	100TH: 100th seconds mode	50
7.4.2.2	Alarm1 and alarm2 control in stop-watch		7.13.2	PI[1:0]: Periodic interrupt	50
	mode	20	7.13.3	RTCM: RTC mode	51
7.4.2.3	Alarm1 and alarm2 function in stop-watch		7.13.4	STOPM: STOP mode control	51
	mode	21	7.13.5	COF[2:0]: Clock output frequency	52
7.4.3	Alarm interrupts	22	7.14	Flags register	53
7.5	WatchDog	23	7.15	Reset register	54
7.5.1	WatchDog functions	23	7.15.1	SR - Software reset	54
7.5.1.1	WatchDog repeat mode		7.15.2	CPR: clear prescaler	56
7.5.1.2	WatchDog single shot mode		7.15.3	CTS: clear timestamp	
7.5.1.3	WatchDog interrupts		7.16	Stop_enable register	
7.6	RAM byte			I2C-bus interface	
7.7	Timestamps		8.1	Bit transfer	
7.7.1	Timestamps interrupts		8.2	START and STOP conditions	
7.8	Offset register		8.3	Acknowledge	
7.8.1	Correction when OFFM = 0			Interface protocol	
7.8.2	Correction when OFFM = 1		9.1	Write protocol	
7.8.3	Offset calibration workflow		9.2	Read protocol	
7.8.4	Offset interrupts		9.3	Target addressing	
7.0. <del>4</del> 7.9	Interrupts		9.3.1	Target address	
7.9.1	ILPA/ILPB: interrupt level or pulse mode			Application design-in information	61
7.9.1	Interrupt enable bits			Internal circuitry	
	interrupt eriabie bits	00	• • •	mornar on outry	04

PCF85263A

Tiny Real-Time Clock/calendar with alarm function, battery switch-over, time stamp input, and I<sup>2</sup>C-bus

12	Safety notes	64
13	Limiting values	
14	Characteristics	
15	Application information	72
16	Test information	
16.1	Quality information	72
17	Package outline	
18	Handling information	
19	Packing information	
20	Soldering of SMD packages	
20.1	Introduction to soldering	
20.2	Wave and reflow soldering	
20.3	Wave soldering	
20.4	Reflow soldering	
21	Footprint information	
22	Appendix	
22.1	Real-Time Clock selection	85
23	Abbreviations	85
24	References	
25	Revision history	86
26	Legal information	

Please be aware that important notices concerning this document and the product(s) described herein, have been included in section 'Legal information'.

# **Mouser Electronics**

**Authorized Distributor** 

Click to View Pricing, Inventory, Delivery & Lifecycle Information:

## NXP:

<u>PCF85263ATL/AX PCF85263AT/AJ PCF85263ATT1/AJ PCF85263ATT/AJ PCF85263ATL/A PCF85263AUKZ OM13516UL PCF85263ATT1/AZ</u>